





Interstate Cooperation for Namami Gange:

Policy and Institutional Challenges and Opportunities



1	Intr	oduction: Why Cooperation Matters?	01
2		torical Trajectory of Water Resources Development (WRD) in India: nging Focus from Developmental Interests to Interdependencies	04
	2.1	History of Water Resources Development in the Ganga Basin	
3	Inte	erstate Conflict and Cooperation in the Ganga Basin	09
	3.1	The track record of interstate river water cooperation in the Ganga basin	
	3.2	Unpacking the nature of interstate river water cooperation in the Ganga Basin	
	3.3	Spatial and Functional Scope of interstate Cooperation Arrangements on the Ganga Basin.	
4	Inte	erstate Interdependencies	16
	4.1	How has India Cooperated: A Framework for Analysing Inter-state Stakes and Interdependencies	
5	Late	ent and Emerging Trends	21
	5.1	The spatial scope of the NMCG and how they enable Cooperation and	
		5.1.1. From Ganga Action Plan (GAP) to National Ganga River Basin Authority (NGRBA)5.1.2. From NGRBA to National Ganga Council (NGC)	
	5.2	Interstate Cooperation and Subnational Institutionalisation for Ganga	
		5.2.1. Empowered Task Force (ETF) Meetings5.2.2 Key Informant Interviews5.2.3 All India State Water Minister's Conference	
6	Cor	ncluding Remarks	29
Ref	eren	ces	32

Table of

	List of Tables
Table 01	Pre-Independence Evolution of the WRD in India
Table 02	Brief description of the historical development of the Ganga & Yamuna canal systems
Table 03	Colonial Agreements on the Ganga Basin
Table 04	Framework for Analysing Interstate Stakes and Interdependencies
	List of Figures
Fig. 01	Decadal frequency of interstate cooperative arrangements
Fig. 02	Forms and Nature of Arrangements
Fig. 03	State's cooperation on Ganga Basin
Fig. 04	River-wise Cooperative Arrangements in Ganga Basin
Fig. 05	Interstate Institutions in Ganga Water Resource Management
Fig. 06	Post-Independence evolution of the water sector administration in India.
Fig. 07	Indian parliamentary questions concerning rivers
Fig. o8	Brief Perspectives & Concerns of Basin States in All India State Water Minister's Conference
	List of Maps
Map 01	Irrigation Canal Network 1901
Map 02	Colonial arrangements in Ganga Basin
Map 03	Interstate Cooperation Arrangements
Map 04	Functional Scope of Interstate Cooperations
	Annexures
Annexure A	Analysis of 47 cooperative instances in the ganga basin with thematic use and spatial coordinates
Annexure B	Inter-State Institutions in Ganga Water Resource Management.
Annexure C	Visual Representation of the Drivers of Cooperation in the Ganga Basin
Annexure D	Empowered Task Force: National Mission for Clean Ganga
Annexure E	All India State Water Minister's Conference

List of Abbreviations

CPR Centre for Policy Research

CPWD Central Public Works Department

CWC Central Water Commission

DPRs Detailed Project Reports

DGCs District Ganga Committees

EYC Eastern Yamuna Canal

ETF Empowered Task Force

EPA Environment (Protection) Act, 1986

FYPs Five-Year Plans

GAP Ganga Action Plan

GoI Government of India

IIT Indian Institutes of Technology

LGC Lower Ganga Canal

MoEFCC Ministry of Environment Forest and Climate Change

MoHUA Ministry of Housing and Urban Affairs

MoJS Ministry of Jal Shakti

NGP Namami Gange Programme

NGC National Ganga Council

NGRBA National Ganga River Basin Authority

NGT National Green Tribunal

NMCG National Mission for Clean Ganga

NRLD National Register of Large Dams

OCEMS Online Continuous Emission Monitoring Systems

O&M Operation and Maintenance

PWD Public Works Department

RBA River Boards Act

STPs Sewage Treatment Plants

SGCs State Ganga Committees

UPPCB Uttar Pradesh Pollution Control Board

UPJN Uttar Pradesh Jal Nigam

UGC Upper Ganga Canal

WRD Water Resources Development

WYC Western Yamuna Canal



Why Cooperation Matters?

India has a fairly long, and unfortunately, less celebrated history of interstate cooperation on water. Even though instances such as the Cauvery water dispute dominate the headlines, efforts for cooperation have been quietly continuing in the background since the pre-independence days (Iyer, 1994). Post-independence, the first three decades saw a steep rise in interstate agreements facilitating cooperation. Incidentally, these decades coincided with major investments in water resources projects through the Five Year Plans (FYPs) (NITI Aayog, respective FYP documents, 1951–2012). This period also saw the emergence of the first disputes over the Narmada, Krishna, and Godayari rivers.

In an increasingly fragmented global order, instances of cooperation have become rarer, and it is the conflicts that dominate the big headlines (Chokkakula, 2014). Conflict over water sources also contributes to these frictions. India is no different. Its relations with neighbours such as China and Pakistan have time and again been strained over transboundary rivers, with the Indus Waters Treaty episode being the most recent. These regional tensions tend to impact interstate cooperation as well (Chokkakula & Prajapati, 2021).

Nurturing an ecosystem for cooperation can have manifold benefits and can also lead to cooperation in other allied sectors. Interstate cooperation can be beneficial in addressing challenges emanating from pressing issues such as climate change. Climate change-related uncertainties have had adverse impacts on water systems and water governance — affecting both water quantity and quality (Milly, 2008). These uncertainties extend not just to evaluating the risks associated with extreme weather events but also to the management of existing storage structures such as dams and the associated flow regimes and allocations (Wolf, 2003). It further exacerbates the likelihood of increased emergence and recurrence of interstate conflicts. Climate change-induced risks call for "a coordinated action, not only between the Centre and states but also between states" (Chokkakula, 2019). In India, there has always been a skewed focus on addressing water quantity issues while paying lesser attention to water quality problems.

Interstate cooperation also lays the groundwork for a more permanent and resilient resolution of disputes. India has historically taken a more judiciary-driven route for the resolution of these disputes (Chokkakula, 2018). Instead of looking at why the cooperation failed in the first place, the attention of both policy thinking as well as scholarship chose to address the challenge of dispute resolution. This 'band-aid' strategic response is baffling because it persisted for decades and remains the primary strategy, but it only provides a short-term solution. This strategy does not address the root causes of lack of cooperation between states, thereby leading to the recurrence of these disputes time and again.

Furthermore, interstate cooperation has an added layer of complexity, as it is embedded in a federal context where cooperation is a prerequisite condition. This context adds an additional challenge of enabling cooperation while working within the intergovernmental structures of federal governance. It brings in the additional dimension of managing Centre-state relations besides those between states. Analysing and sustaining an ecosystem for enabling cooperation entails engaging with a range of dimensions — federal governance, politics, and institutions — which this paper explores in the subsequent sections.


This web of interdependencies is key to understanding the importance of creating and sustaining a resilient ecosystem of cooperation between states. Cooperation on aspects of water quantity, infrastructure, etc., can shift focus to critical aspects of water quality. The importance of political will in driving cooperation for transboundary rivers as drivers of cooperation – where do interdependencies come into the picture? The importance of centre-state relations/cooperation in ensuring cooperation in the long term – how does India's federal nature impact this cooperation – are cooperation agreements always Centre-driven or are they mostly the result of bilateral cooperation between states with minimal role of the Centre (Chokkakula, 2015).

In an attempt to delineate the intricacies of interstate cooperation and expand on how states cooperated over water resources, this paper starts with tracing the historical evolution of water resources development in pre and post-independence India, with a specific focus on the Ganga basin. It then goes on to discuss the instances of conflict and cooperation in the Ganga basin – mapping their form, nature, and spatial and functional scope. For the purpose of this study, our focus is only on the episodes of cooperation in the Ganga basin and why states cooperate. To assess the underlying interdependencies which drive these instances of cooperation, the paper proposes a framework adapted from the scholarly contributions of Fischer & Jager (2020), Sadoff and Grey (2005), and Le Marquand (1977) and modified based on the contextual specificity of the Ganga basin. This framework helps in identifying the enablers of interstate water cooperation and understanding the reasons for cooperation between states.

Additionally, we delve into the institutional architecture which enables and sustains this subnational cooperation. The intricate interdependencies among the states and the number of cases where the Ganga basin states have cooperated lay the groundwork for identifying and developing a potential ecosystem for cooperation among these states in the development and management of interstate rivers, albeit with certain limitations. Most of the cooperation has been driven by water quantity and supply augmentation concerns. However, there are encouraging developments.


The flagship Namami Gange Programme (NGP) has received extensive attention for its unprecedented budgetary allocation and unique institutional structure. NGP's institutional structure is devised to reinforce the importance of the political and developmental concerns of the state's subnational governments and actively work with them. Besides, from 2023 onwards, the All India State Water Minister's Conference has been a useful forum to advance a national vision for India's long-term water security under its unique federal context. The analysis of the NGP and the proceedings from the Conference reveals a latent and encouraging shift in perspectives of the states towards environmental and ecological considerations in their respective water resources management. However, this shift is still at a nascent stage, and the states are slow in institutionalising the NGP into their respective plans and policies.

We delve into the possible reasons for this gradual and intermittent ownership of the NGP from the states. We argue that the existing cooperative arrangements pertaining to water resources projects have produced indispensable interdependencies among the Ganga basin states in sharing benefits and managing risks. These arrangements offer invaluable lessons for the states and the centre to conceptualise an enabling ecosystem wherein states could cooperate in improving the water quality and the ecological health of the Ganga basin.



Changing Focus from Developmental Interests to Interdependencies

In the pre-independence period, the water and irrigation sector received less focus until the great famine in British India in 1858 (Mishra et al., 2019). The Public Works Department (PWD) began limited activity under the Government of India (GoI) Act 1858, transferring the power from the East India Company to the British Crown. The GoI Act 1919 limited the central government's role to an advisory and coordinator capacity by transferring the subject of irrigation to the provincial government. The Central Board of Irrigation was set up in 1927, to take a more robust stand on limiting the Centre's power. With the increasing workload, the Department of Labour was assigned the irrigation and power sector to overcome the shortcomings.



Source: TREADS Analysis

With the Independence in 1947, reform and expansion took place in each sector, creating the Department of Works, Mines, and Power, focusing on expanding the domains of Irrigation and Power. In 1951–1952, with the first independent government of India, a dedicated ministry was created as the Ministry of Irrigation and Power, marking water as a national development priority (Dhawan, 1993).

Between 1954-1980, the sectoral focus and institutional development increased with the establishment of the Flood Control Board, highlighting a new concern for flood management. The Irrigation Commission was constituted in 1969 to plan a comprehensive irrigation department, which led to further restructuring of separate departments and ministries focused on bringing irrigation to the Central government's agenda as a standalone ministry (GoI, 1972).

800-1947

History of Water Resources Development in the Ganga Basin

Water resources development in the Ganga Basin has historically contributed to the agricultural development of some of the key basin states at an unprecedented scale. In particular, the Ganga and Yamuna Canal systems — namely, the Western and Eastern Yamuna Canals (WYC and EYC) and the Upper and Lower Ganga Canal (UGC and LGC) — date back to the pre-colonial period but underwent a significant transformation under British rule. The development of this vast network of canals not only transformed the irrigation and economic landscape of the region but also shaped the institutional ecosystem for water resources development (*See Map o1*).

The origin of the Central Public Works Department (CPWD) was conceived by the British government during the 1850s for the development of irrigation and other infrastructure (Arnold, 2018). The development of irrigation was driven by its geographic and economic potential for revenue generation for the British colonial government. This explains the early development of irrigation in provinces such as the Punjab, United Provinces, Sind, and Madras (Whitcombe, 2008). Hardiman (2007) and Whitcombe (2008) further show that by the 1860s, the vast canal networks, along with the sluices and distributary channels, were under the direct control of the PWD, which was relatively independent and directed the production of the commercial crops such as wheat, sugarcane, indigo, cotton, and rice in this region. In this aspect, the Ganga basin has historically been highly developed, albeit with a skewed focus on supply augmentation (Chokkakula, 2019). The following table shows Brief description of the historical development of the Ganga & Yamuna canal systems.

Table 02: Brief description of the historical development of the Ganga & Yamuna canal systems

UGC

The construction was initiated by the then British government in the 1840s to address drought and famine in the western part of the current state of Uttar Pradesh (Jain et al. 2007).

LGC

To irrigate the lower portion of the Ganga-Yamuna doab, a project was sanctioned, and work started from 1872 onwards by constructing a new canal from the main Ganga Canal in Narora, Bulandshahr (Jain et al. 2007).


WYC & EYC

The origin of the Western Yamuna Canal dates back to Feroz Shah Tughlaq, who constructed the WYC. During the British period, the canal was realigned and repaired from 1821 onwards (Jain et al. 2007).

The earliest canals in Northern India of which any record exists are the old canals that take off from both banks of the Yamuna (Mukherjee, 2007).

Source: TREADS Analysis & CWC (2015)

Whitcombe (2008) further highlights that there had been an attempt during the 1920s and 1930s by the colonial government to diversify the use of the water resources in India, especially the hydropower sector, for prospective revenue income. However, lack of power demand in the rural areas was a major impediment in this process, and irrigation continued to be the sole driving force for water resource development in the Ganga Basin (Ray, & Pullabhotla, 2023).



Source: Hardiman (2007)

large-scale developments These also required various arrangements between the erstwhile British government/provinces and those of the princely states as well as among the provinces. In most cases, the agreements were aimed at water and costsharing arrangements, specificity of repair work following flood disasters, supply of water during the crop sowing Kharif season. and dispute resolution mechanisms. These arrangements also represented the control of the colonial government over the irrigation infrastructure and the requirement of payments and other penalties to them by the princely states (Basu, 2022).

The Central Water Commission (CWC) produced a legal instrument (Legal Instruments on Rivers in India, Vol. 3, Part II) which shows three such arrangements, and the table below provides a brief synopsis of the same.

Table 03: Colonial arrangements on Ganga Basin

Year	Basin	Arrangement	Scope of the Arrangement	
1892	Yamuna	British Government and the Princely State of Jhind	 Regulation on irrigation supply from the Western Jumna Canal. It defined allocation rights, maintenance responsibilities, and dispute-resolution mechanisms. 	
1925	Yamuna	Punjab and the United Provinces	Repairs and alterations below the Eastern Jumna sluices, regulating, repairing the bunds, and construction of spurs on account of the 1924 Yamuna floods.	
1943	Yamuna	Government of East Punjab (British Province) and Princely State of Jhind	It defined control and management, regulation and distribution of supplies, assessment collection and payment to Punjab by the princely states, penalties, and dispute resolution protocols of the Sundar Sub-Branch of WYC.	


Source: TREADS Analysis & CWC (2015)

The colonial development of the Ganga Canal reveals three key themes:

- The large-scale irrigation focus in the Northwestern Part of the Ganga Basin which still remains one of the most agriculturally productive regions in India.
- The institutional evolution, such as the PWD represented a hydro bureaucracy with a sole focus on supply augmentation and revenue maximisation the supply side focus is still embedded in the institutional culture of the State Water Resources Department.
- Growth of water-intensive commercial crops in the region, such as sugarcane and rice, through irrigation development is still continuing.


PUNJAB UNITED PROVINCES AJMER GWALIOR BIHAR BENGAL RAJPUTANA CENTRAL INDIA EASTERN STATES CENTRAL PROVINCES 1941 State Boundary Ganga River and tributaries Ganga Basin Source: TREADS Analysis & CWC (2021)

Map 02: Colonial arrangements on Ganga Basin



The colonial agreements in many ways reflected deeply inequitable arrangements where the revenue maximisation was a key objective for the erstwhile British government (Whitcombe, 2008). However, the purpose of the post-independence cooperative arrangements are vastly different. Besides the territorial reorganisation of the basin states, India's subnational political and developmental imperatives required some interstate arrangements to harness the potential of interstate rivers. In other words, the Ganga basin states have seen merit in cooperation.

The Ganga and its tributaries have formed a large, flat, and fertile plain in North India. The availability of water resources, the suitable soil and climatic conditions, and the historical contribution of irrigation development have made the region agriculturally productive (India-WRIS 2012). At the same time, the basin region has one of the highest population densities in the country and grapples with varied environmental risks — of which flooding and water pollution are the most prominent. These conditions have been favourable to the Ganga basin in creating an ecosystem of interstate cooperation whereby the basin states share costs and benefits and jointly manage water resource projects. Contrary to the instances of interstate water disputes that are prevalent in the peninsular rivers — such as the Cauvery and the Krishna — the Ganga basin states have historically cooperated on a number of occasions.



3.1

The track record of interstate river water cooperation in the Ganga Basin

Volume 3 of Legal Instruments on Rivers in India, published by the CWC in 2015, compiles all the interstate river water agreements or arrangements. It may also be noted that all cooperative arrangements are not agreements under legal jurisprudence—it varies between formal agreements and informal arrangements reached during various high-level convenings. The Volume lists a total of 160 entries across all the interstate river basins in India.

In 2018, the Centre for Policy Research (CPR), in collaboration with the CWC, took up the task of updating the track record of interstate cooperation. The Volume (under review), updated in 2021, led to identifying 32 more agreements. It may be noted that for the purpose of this study, the updated version has been taken into account that corresponds to 47 entries of cooperative arrangements in the Ganga Basin that are varied in nature. At the same time, there are a few caveats when it comes to explaining and analysing these interstate cooperative arrangements:

- They are not exhaustive. The arrangements/agreements included here are only those that are reported by the states to the CWC. Some additional instances of these cooperative arrangements were collected by the TREADS Initiative during their field visits. In many cases, the states underreport the existing arrangements.
- The cooperative arrangements and their components, including the quantity of benefits and costs specified — do not always translate into the actualisation of projects and vary widely.
- Some of the arrangements are associated with multiple projects and are spatially varied. For the purpose of spatial representation of each instance, we have selected a location that is in proximity and which tentatively covers multiple projects. For example, the Chambal system corresponds to the Gandhi Sagar, Rana Pratap Sagar, and Jawahar Sagar projects shared by Madhya Pradesh, Uttar Pradesh, and Rajasthan.

Detailed analysis of 47 cooperative instances in the Ganga basin with thematic use and spatial coordinates is attached in Annexure A.

3.2

Unpacking the nature of interstate river water cooperation in the Ganga Basin

The nature of the cooperative arrangements in the Ganga Basin presents significant variation in both spatial and functional scope. The cooperation between the states has resulted in some of the most significant and consequential large-scale water resources projects in the Ganga river, enabling a transformative impact on the region's social and economic development. The Fig. or outlines the instances where Indian states cooperated with each other post-independence in the development of the Ganga basin. It may be noted that for the purpose of analysis only post-independence cooperation has been considered.

It is interesting to note that there has been a steady growth of interstate cooperation post independence which peaked in the decade of 1970-80 before a sharp decline from the 1980s onwards. This increase in cooperative arrangements is attributed to a combination of factors. First, the State Reorganisation Act of 1956 (GoI, 1956) — where state boundaries were redrawn based on a linguistic line. The reorganisation led to juxtaposing new territorial and political units on the hydrological basin boundary of Ganga, requiring states to cooperate for joint development. The decades of the 1950s and 1960s also had several interstate conferences for irrigation development over interstate rivers, led by the Planning Commission (Chokkakula & Prajapati, 2021).




Fig 01: Decadal frequency of interstate cooperative arrangements

Source: TREADS Analysis & CWC (2021)

The nature of the agreement also varies widely. There are both bilateral agreements (among states without the Centre's involvement) and those actively facilitated by the Centre. Some agreements/arrangements are also outcomes of the formal mediation processes by the Centre or the tribunals, sometimes in the form of notifications or orders by the Centre (Chokkakula & Prajapati, 2021). In addition, decisions arrived at interstate meetings became a key enabler of multiple interstate water resources projects. River Boards — such as Chambal Board (now formally known as the Madhya Pradesh–Rajasthan Inter State Control Board) — became important avenues for consensus building on inter–state water matters.





Fig 02 Forms and Nature of Arrangements

Source: TREADS Analysis & CWC (2021)

3.3

Spatial and Functional Scope of the Inter-State Cooperation Arrangements on Ganga Basin



The mapping of interstate cooperation agreements (Map o3) highlights an interesting trend. The cooperation among the states resulted in a number of water resources projects, the majority of which are located in the interstate tributaries and not on the main stem of the Ganga basin. In particular, the sub-basins/tributaries of Ganga — Yamuna, Chambal, and Betwa — are where most of the inter-state projects are located and which required cooperation amongst the states. Across these sub-basins, select states such as Rajasthan, Madhya Pradesh, and Uttar Pradesh are party to the majority of the agreements or decisions (Fig. o3).




Fig 03: State's cooperation on Ganga Basin

Source: TREADS Analysis

These instances of interstate cooperation have an expansive functional scope — ranging from allocative and distributional issues, cost sharing, and coordination mechanisms for joint development (Map 04).

However, there have been no instances where states cooperated in managing water pollution or improving the ecological health of the river system. A closer reading of these agreements suggests that the primary motivation of the states to cooperate has been skewed towards water quantity-related aspects rather than quality — indicating that in India's federal context, the developmental concerns of the states took precedence over ecology since independence.




Fig 04: River-wise Co-operative Arrangements

Source: TREADS Analysis

However, a longitudinal analysis reveals important shifts in the ways water resources are managed — from resource extraction and revenue generation considerations towards developmental and environmental risk concerns. For example, addressing drought risks and water pollution in recent times. The cooperative arrangements reveal that although over a period of time the states have been territorialised on multiple occasions, they are mutually dependent in managing shared water resources. In the next section, we discuss how states are interdependent and what lessons we can draw from these interdependencies in conceiving an ecosystem of inter state cooperation for river rejuvenation.



4.1

How has India Cooperated: A Framework for Analysing Interstate Stakes and Interdependencies

These developmental concerns of the states, coupled with the interjurisdictional nature of the Ganga basin system, have produced a degree of interdependence among them that transcends beyond allocation and distribution of water — from hydropower distribution among states to flood risk management and incentives in jointly developing and managing large-scale water resources projects. To better understand this complex interplay, this study has developed a framework to map attributes driving cooperation among the states. Specifically, the framework is developed by drawing from the work of Fischer & Jager (2020), Sadoff and Grey (2005), and Le Marquand (1977) and modified based on the contextual requirements of this study.

This framework identifies five key drivers that create interdependence among the states:

- Water/environmental risks and stressors: Cooperation as an outcome of water-related stress/risks. Many of the Ganga basin states are highly vulnerable to flooding. The downstream states are subjected to acute flooding and bank erosion challenges. For example, Bihar and West Bengal.
- **Benefit Sharing:** Cooperation as an outcome of shared water resources/power distribution and allocation. From pre-independence, the Ganga and its tributaries support an intricate and vast network of canal systems and are one of the most important contributors to India's hydroelectric power generation. Many of these benefits are derived from large-scale multipurpose interstate projects whose benefits are distributed across state boundaries. As per the India-Water Resources Information System database, there are 784 dams situated in the Ganga basin, out of which 158 dams are included in the National Register of Large Dams (NRLD), 66 barrages, 92 weirs, and 45 lift schemes. These contribute to a total of 478 medium and major irrigation projects, 39 hydroelectric projects, and 56 powerhouses. The benefits are largely distributed.
- Cost Sharing: Financial incentives as an outcome of joint development of projects. A number of these projects have been financed jointly by the states with and without the financial support from the centre. The joint development of interstate projects is incentivised through cost sharing.
- **Coordination Demands:** Creation of interstate river boards/authorities as an outcome of coordination demands. The joint development of projects often involves benefit distribution on a pro rata basis or based on their hydrological/catchment area contribution. In the efficient management of these projects, a joint river management board/authority for implementation and coordination becomes central.
- **Reorganisation of State Boundaries:** Interstate and center-state political groupings.

Subsequently, the framework is used to assess the 47 instances of cooperation. It is important to note that, when analysing the drivers of this subnational cooperation, some of the subnational agreements may correspond to one or more of these attributes. Furthermore, in addition to assessing these drivers, we analyse the diverse federal and interstate entities — such as river boards and authorities — including their origin, legal instruments of constitution, and respective functional mandates. This allows us to highlight how these institutional arrangements have produced functional interdependencies among states to govern the interstate rivers (*Table 04*).

Table 04: Framework for Analysing Inter-state Stakes and Interdependencies

Attributes Description		Agreements	
Water/environmental risks and stressors	Recurring floods and droughts.	Ken-Betwa-Sone: KBS3, KBS4 Hooghly: H1	
Benefit Sharing	Functional interdependencies leading to joint development and sharing of benefits.	Ken-Betwa-Sone: KBS1, KBS2 Yamuna: Y6, Y7, Y8, Y4, Y9, Y13 Chambal: C1, C2 Sone: S1, S3, S4, S8, S9, S10, S12 Betwa: B1, B3, B4, B5 Hooghly: H1 Karmanasa: K1 Gandak: G1	
Cost Sharing	Cost sharing among the states.	Ken-Betwa-Sone: KBS1, KBS2, KBS3, KBS4 Yamuna: Y5, Y6, Y7, Y8, Y9, Y10, Y12 Chambal: C3, C4, C5, C6 Sone: S1, S2, S4, S6, S7, S8, S10, S11 Hooghly: H1 Karmanasa: K1 Betwa: B2, B3, B5	
Coordination Demands	Joint institutions and engagement of the central government.	Ken-Betwa-Sone: KBS3, KBS4 Yamuna: Y4, Y5, Y8, Y9, Y10 Chambal: C2, C7, C8, C9 Sone: S5, S8, S10 Betwa: B2, B5, B6	
Reorganisation of State Boundaries	Favourable inter-state and centre-state political groupings.	Ken-Betwa-Sone: KBS3, KBS4 Chambal: C1, C4, C5 Sone: S1	

Source: TREADS Analysis *Yamuna: Y1 - Y4 arrangements are Pre-Independence. Hence excluded.

Refer to Annexure C: Visual Representation of the Drivers of Cooperation in the Ganga Basin

The interstate bodies — ranging from river boards to authorities — have proven to be indispensable to respond to the complex water governance challenges in the Ganga basin. These institutions have been instrumental for the state to collaborate effectively, promote joint planning of infrastructure, build consensus, and coordinate the execution of projects. In effect, all the interstate joint bodies/river authorities/boards have one component in common — representation from the central government.

However, their spatial and functional scope has been limited, and their constitution has been ad hoc in managing compounding and cascading water-related risks and pollution. These interstate bodies have been constituted with an exigency-based approach and are context-specific. Table o4 shows how most of the boards were drawn from multitudes of legal provisions and not from the River Boards Act (RBA) 1956, which was specifically enacted by the Parliament under Article 262 of the Indian Constitution. The RBA 1956 was specially designed to constitute interstate river boards and is vested with wide-ranging functions for both the development and regulation of interstate rivers. One of the crucial functions of these boards was the prevention of pollution of the waters of interstate rivers. This structured approach in the constitution of river authorities was not taken, and water quality and quantity have been dealt with separately. (*See Fig. 05*)

The Current Shifts: Progressive Policymaking

From 2014 onwards, there has been a visible shift. In 2014, GoI launched the NGP with an unprecedented outlay of INR 20,000 crores. The National Ganga River Basin Authority (NGRBA) and the National Mission for Clean Ganga (NMCG) were shifted out of the Ministry of Environment Forest and Climate Change (MoEFCC) to the Ministry of Water Resources, renamed as the Ministry of Water Resources, River Development & Ganga Rejuvenation, stressing the importance attached to cleaning the Ganga. In the next section, we will revisit how the NGP is a promising step towards interstate cooperation for water quality management and the bottlenecks it is facing in realising that objective.

The identification of these interdependencies is crucial to presenting a case on how states could be incentivised to cooperate with each other to address water quality issues and the improvement of river ecology. As a preview for the next section, we note that states themselves are required to progressively reform their subnational water policies and institutions to incorporate ecological sensitivities and incrementally shift from a skewed focus on water quantity and supply augmentation. In the next section, we analyse the evolving and emerging trends where India is prioritising water quality and ecology in its broader water governance framework — both at the national and subnational levels.

Fig 05: Inter-State Institutions in Ganga Water Resource Management

2016

1976

1972

Ganga Flood Control Commission

Established to formulate and implement comprehensive flood management plans for the Ganga Basin through coordinated inter-state measures.

National Mission for Clean Ganga (NMCG)

Formed under the Namami Gange Programme (NGP) to replace the National Ganga River Basin Authority (NGRBA) and oversee the rejuvenation of the Ganga.

1994 Upper Yamuna River Board

An MoU was signed amongst the five basin states of HP, UP, Haryana, Rajasthan, and Delhi for sharing the waters of Upper Yamuna.

Betwa River Board

The December 9, 1973, meeting b/w UP and MP led to the establishment of a tripartite control board, resulting in the creation of the Betwa Board for overseeing the Rajghat Dam and Powerhouse project, funded by both states and responsible for reservoir regulation.

1948

Damodar Valley Corporation

The Damodar Flood Enquiry Committee suggested the creation of an authority similar to the Tennessee Valley Authority, USA. A proposal was accepted by the committee for multipurpose development of Damodar Valley.

1976

1955

Chambal Control Board

To ensure efficient, economic and early execution of Chambal Valley Development projects.

Bansagar Control Board

On September 16, 1973, UP, MP, and BR agreed to utilise the waters of the river Sone, leading to the 1976 establishment of the Bansagar Control Board by the Ministry of Agriculture and Irrigation to oversee the Bansagar Project in MP.

Source: TREADS Analysis

For detailed analysis, refer to Annexure D: Inter-State Institutions in Ganga Water Resource Management.



Water resources management in post-independence India has primarily been driven by supply-augmentation considerations, a continuation from the colonial period. This is reflected in how water resources have been located in the different ministries since 1947 (Fig. 06). In the initial period, there were no separate ministries managing the country's water resources, and instead, water governance was subsumed under the subjects of irrigation, power, energy, and agriculture. This positioning of water resources with energy and irrigation reinforces water as a resource that has been considered from the point of view of extraction and supply for India's developmental needs. It was in 1985 when the Ministry of Irrigation was renamed as the Ministry of Water Resources , albeit without a visible shift in its mandate and objectives when it comes to water quality management and protection and conservation of water resources.

Fig. o6: Post-Independence evolution of the water sector administration in India

Ministry of National Resources and Scientific Research

It took over the subject of Irrigation and Power from the Ministry of Works, Mines, and Power.

Ministry of Agriculture and Irrigation

The Department of Irrigation was set up under the new Ministry, consequent upon the bifurcation of the erstwhile Ministry of Irrigation and Power.

Ministry of Irrigation

The Ministry of Energy and Irrigation was bifurcated, and the erstwhile Department of Irrigation was raised to the level of a Ministry for a coordinated and comprehensive view of the entire irrigation sector.

Ministry of Water Resources

The Ministry of Irrigation and Power was bifurcated, and the Department of Irrigation was re-constituted as the Ministry of Water Resources.

This recognition of the necessity of planning for the development of the country's water resources in a coordinated manner resulted in a change in the character of the Ministry and the Ministry assumed a nodal role regarding all

Ministry of Water Resources, River Development & Ganga Rejuvenation

The Ministry of Water Resources was renamed to "Ministry of Water Resources, River Development & Ganga Rejuvenation", making it the NGRBA for conservation, development, management, and abatement of pollution in the river Ganges and its tributaries.

Departn Created o

Department of Works, Mines, and Power

Created on the recommendation of the Secretariat Reorganization Committee, which looked after the subject of Irrigation and Power.

952

Ministry of Irrigation and Power

A separate Ministry was set up to look after the subject of 'Irrigation.'

(Jan)

Ministry of Energy and Irrigation

The Department of Irrigation came under the newly formed Ministry.

1985 (Jan)

Ministry of Irrigation and Power

The Ministry of Irrigation was once again combined under the Ministry of Irrigation and Power.

Ministry of Drinking Water and Sanitation

In 1999, the Department of Drinking Water Supply (DDWS) was formed under the Ministry of Rural Development for focused attention on drinking water and sanitation. Later it was renamed as the Department of Drinking Water and Sanitation in 2010.

Nodal department for the overall policy, planning, funding and coordination of programmes of drinking water and sanitation in the country.

019

Ministry of Jal Shakti

It consists of two Departments i.e., the Department of Water Resources, River Development and Ganga Rejuvenation (Jal Sansadhan, Nadi Vikas Aur Ganga Sanrakshan Vibhag) & Department of Drinking Water and Sanitation (Peya Jal Aur Swachhata Vibhag).

Source: TREADS Analysis

The paradigm shift came in 2014 when 'Ganga Rejuvenation' was incorporated into the Ministry's mandate. The merger indicated the progressive policy shifts where water quality and ecological health have been equally prioritised along with the quantity in India's broader water resource governance framework. This observation has also been validated by the work of Azhoni et al. (2022), where they analysed Indian Parliamentary Questions (Lok Sabha) concerning rivers and the changing priorities of the central government in managing river basins over the last decades. They argue that there is a visible shift in focus by the parliamentarians — from large-scale reservoirs, irrigation, and hydropower towards increased attention on inter-basin water transfers, river conservation, and pollution (*Fig.* 07).




Fig. 07: Indian Parliamentary Questions concerning rivers

Source: Azhoni et al. (2022)

5.1

The spatial scope of the NMCG and how they enable Cooperation and Coordination

The launch of the NGP was a critical point of transition, paving the way for robust interstate and centre-state cooperation in managing transboundary environmental pollution, which we will discuss in the next section.

5.1.1 From Ganga Action Plan (GAP) to National Ganga River Basin Authority (NGRBA)

The GAP was launched in 1984 with a limited mandate. The goal of the GAP in addressing point source pollution was straightforward: "intercept, divert, and treat" wastewater generated in urban centres. However, GAP proved to be inadequate in tackling the complexity of water pollution in the Ganga. One of the key arguments for the underwhelming outcome of the GAP was the limited role and inadequate resources of the state government. The insufficient institutional capacity of the state governments was unable to address the complex water pollution challenges in the Ganga basin. The Ganga River Basin Management Report, produced by a consortium of seven Indian Institutes of Technology (IITs), in their SWOT analysis of the GAP observed, "... GAP missed many aspects such as the need for analysing policy and legal aspects of center-state relationships, implementation of the 74th amendment to the Indian Constitution, and State Government-ULBs relationships, as well as the convergence of policies adopted for implementing GAP with the broader developmental policies." To address this gap, the Government of India constituted the NGRBA.

The NGRBA was constituted by the Environment (Protection) Act, 1986 (EPA), to increase the scope of cooperation and coordination on the Ganga. NGRBA was designed to take a holistic approach as a unit of planning and institutional restructuring, focusing robustly on a basin-wide approach to river management. In 2014, the Authority was reconstituted, designating the MoEF&CC as the nodal agency for programme oversight and entrusting the NMCG with executive responsibility for project implementation and financial management. However, the programme lacked financial resources and an adequate legal and institutional structure in addressing water pollution at the basin scale.

5.1.2 From NGRBA to National Ganga Council (NGC)

In 2016, the GoI issued the River Ganga (Rejuvenation, Protection and Management) Authorities Order of 2016 (Ganga Notification, 2019). This Order dissolved the NGRBA, and the NMCG was accorded the status of an authority. A National Ganga Council (NGC) was created to oversee and guide the NMCG. The NGC is a representative and deliberative body with extensive political heft. It is headed by the Prime Minister with the Chief Ministers of the riparian states and other ministers as members. NGC functions through an Empowered Task Force (ETF) headed by the Union Minister for Jal Shakti and an Executive Council headed by NMCG's Director General with extensive financial and regulatory powers. The 2016 Order also recognises the subnational governments as partners by creating State Ganga Committees (SGCs) and District Ganga Committees (DGCs) with their functions laid out for implementing the NGP.

5.2

Interstate Cooperation and Subnational Institutionalisation for Ganga Rejuvenation Cooperation and Coordination

The five-tiered structure (See fig. 08), as proposed under NGP, is yet to function to its full potential. This is linked to an absence of subnational ownership of the programme, reflected by the non-existence of adequate basin-state-level legal, institutional, and budgetary responses. In contrast to the interstate cooperation for large-scale water resources projects, as was discussed in the previous section, there are few incentives for the states to build mechanisms and jointly implement a river rejuvenation programme.

NGP is largely a centrally sponsored programme. In this view, the endurance of the NGP is, to a large extent, dependent on two aspects. First, the ability of the states to cooperate with each other in driving the programme once its mission life ends. For example, in the case of data sharing, there is no procedural framework for the states to share data with each other. Secondly, the states are also required to institutionalise the programme into their subnational plans and policies and in reorienting the institutional culture of their Water Resource Departments, moving from a sole focus on supply augmentation towards incorporating pollution risk management in their mandate. The weak subnational response is reflected in the judiciary-driven pollution management, such as the NGT, which frequently directs states to comply with its orders on various river pollution-related measures.

In the recently held Maha Kumbh (2025) in Prayagraj, Uttar Pradesh, the National Green Tribunal (NGT) took cognisance and appointed a Joint Committee (Report by District Magistrate, Prayagraj, 2022), which submitted a report through the Uttar Pradesh Pollution Control Board (UPPCB), revealing that the untreated sewage through the untapped drains was flowing directly into the river and there was a significant gap in the generation and treatment of sewage. It was found that out of 76 drains, 37 were tapped by UP Jal Nigam (UPJN), which are being treated by 10 Sewage Treatment Plants (STPs), and the discharge was released directly into the rivers.

However, in the last few years, there is an emerging trend where states are increasingly raising the concerns of environmental pollution affecting the state's water management. For instance, Delhi's drinking water supply gets severely disrupted with an increase in upstream pollution load. The discussion presents a case where analysing the states' concerns, their political and developmental priorities, and evolving interest in water resources management remains key in conceiving an ecosystem of cooperation for collective action by the Ganga basin states. In order to do that, we analyse:

- 1. ETF meetings where the State and the Central Ministers interact across sectors on key issues and priorities for Ganga rejuvenation (5.2.1.);
- 2. Key informant interviews (5.2.2.); and
- 3. The All India State Water Minister's Conference where the central government is working with the states to formulate India's Water Vision 2047 (5.2.3.).




Fig. o8 - NMCG's five-tiered structure

Source: NMCG

5.2.1 Empowered Task Force Meetings

The NGC and the ETF offer a two-tier system wherein the political and technical concerns of the states are represented. Although the NGC has only met twice since 2016, ETF meetings are convened frequently by the NMCG. In this section, we analyse the proceedings of these meetings from 2015 to 2025 to identify the perspectives of the states as well as the mechanisms through which NMCG supports the states in the implementation of the NGP. The following trends emerged from our analysis, and the detailed proceedings of the ETF meetings during the period of 2015 to 2025 can be accessed in **Annexure D**.

In terms of the proceedings, the Central ministries have shown domination in setting the agenda (conducting meetings and deciding sectoral financial allocations), while state-specific bottlenecks, particularly those related to political and financial issues, were rarely discussed. The majority of the meeting time and agenda were devoted to progress monitoring, with relatively fewer or limited discussions or advocacy for state-level concerns. The states' inputs were mostly procedural, where they mention the compliance status rather than mentioning their local challenges or political impediments and concerns. Therefore, the focus is shifted to central directives and achievements by sidelining granular realities on the ground faced by the states.

- From 2017 to 2025, the ETF meetings on the NGP primarily focused on the fund's utilisation, project progress within the states, and stakeholder participation across the Ganga basin states. Each basin state is responsible for the implementation of their statewise projects under NGP funded by NMCG. The coordination with multiple central ministries and state governments ensures the convergence of funding and project synergies.
- Across the basin states, the focus was primarily on identifying and mapping the nallahs, wetlands, and small water bodies for rejuvenation. With the coordination of ULBs, various plans or advanced action plans are prepared with pending approvals from the state governments. The STP projects were widespread, especially in UP and Bihar, with over 136 STP/I&D (inlet and drainage) projects reported during the 2018–2021 phase. Water Quality monitoring through Online Continuous Emission Monitoring Systems (OCEMS) was mandated for STPs with >1 MLD capacity.

5.2.2 Key Informant Interviews

The proceedings from the ETF meetings provide limited perspectives on how the centre-state or interstate concerns are addressed. To get a more granular understanding, key informant interviews and practitioners' perspectives have proven to be useful. Some observations from these consultations are as follows:

- The interstate and the centre-state political alignment, although useful for implementing large-scale programmes such as the NGP, are not always true. The complexities are often layered such as between the state and the local governments. Similarly, on many occasions, even if the political alignment between the centre and the state has not been favourable, project implementation has not suffered.
- States on many occasions have been criticised for their capacity in the preparation of the Detailed Project Reports (DPRs) and delays in land acquisition for the construction of STPs. However, this challenge is seldom discussed in the ETF/other forums and is instead discussed in various informal-level discussions.
- The Central government often uses various levers fiscal, legal, and institutional to nudge states to cooperate in the implementation of the NGP. For instance, the central government has not only provided extensive capital expenditure support in implementing the NGP, but significant Operation and Maintenance (O&M) costs are also borne by the Centre. This has often resulted in an institutional culture where deployment of finance has been central to the NGP. In addition, NMCG has also deployed its role as an authority in influencing the states' water resources policy. For instance, NMCG amended the 2016 authority notification to permit the discharge of treated sewage into the river, canal, or water bodies.

5.2.3 All India State Water Minister's Conference

In the last two years, the forum for the All India State Water Ministers' Conference has received significant political attention. The Conference, hosted by the MoJS, gave a platform to the states to highlight their respective crucial aspects of water management, including effective governance, transboundary cooperation, innovative financing, and community participation. We transcribed and analysed the proceedings of the Conference to highlight the major challenges, progress, and concerns of the states in their management of water resources. It may be noted that only the Ganga basin states have been considered for the purpose of this analysis. The detailed proceedings of the Conference between the period of 2015 to 2025 can be accessed in **Annexure E.**

Haryana

- Water Scarcity in Southern part of Haryana aims at 100% reuse of wastewater by 2028.
- Challenges of fragmented governance. The Model State Integrated Water Resources Plan was formulated on the basis of block-level data of demand and supply in 2023. There were significant concerns regarding asset management pertaining to drinking water and irrigation supply.

Delhi

- High dependency on external water sources: 52% of Delhi's water is non-revenue water, which is mainly because of the ageing infrastructure and mismanagement.
- Key issue raised: Yamuna water pollution.

Uttarakhand

- Focus on Springs and Water Bodies: The govt. established the Spring and River Rejuvenation Authority (SARA) to protect and revive various water bodies, including small and large rivers, reservoirs, and rain-fed streams.
- Use of technology: Deploying technology such as GIS technology, GPS, and drones for terrestrial assessment, monitoring flow rates, and water quality. Geo-hydrological studies and mapping help identify recharge areas, forming the basis for long-term conservation plans.

Uttar Pradesh

- Flood Plain Zoning and regulations for major rivers to control encroachment and pollution are maior considerations after the NGT's directives have led to the scientific determination of flood zones for rivers like Ganga, Yamuna, Gomti. Ramganga, Betwa, Ghagra, and others using high-resolution remote sensing.
- Advancing urban river rejuvenation through planning and implementation of the Urban River Management Plans (URMPs).

Rajasthan

Acknowledges the importance of inter-state river water cooperation between Madhya Pradesh and Haryana in addressing Rajasthan's water challenge.

Madhya Pradesh

Water overuse: Irrigation for agriculture and the use of technology such as SCADA (Supervisory Control And Data Acquisition) are major focuses.

Bihar

- Ensuring safe drinking water in arsenic, fluoride, and iron-affected areas. High focus on water supply projects before 2047 to shift from groundwater to surface water supply using modern technology and smart meters.
- Flooding in North Bihar is a major issue, with the Kosi River (a tributary of the Ganga) frequently changing course, causing erosion and destruction. Long term solution by building high dams through Indo-Nepal Cooperation is required, as well as the strengthening of embankments.
- Asset Management: Bihar Embankment Asset Management System is a GIS-based web portal for scientific planning, flood forecasting, and disaster impact assessment that has been useful

West Bengal

- Focus on agriculture and irrigation development.
- Challenges with water reuse and greywater management.
- Fragmented water legislation in the state.

Fig. 8 - Brief Perspectives & Concerns of Basin States in All India State Water Minister's Conference

Source: Compiled from the proceedings of the Second All India State Water Minister's Conference, February 2025



The Ganga Basin is one of the most complex river systems in the world for governance and management. It has one of the highest population densities, with significant variation of socio-economic indicators, both at the subnational level and among districts within the same state. Agriculturally, it remains one of the country's most productive regions, historically and presently. The colonial development of large-scale irrigation has shaped both the irrigation and institutional structures of its state water resources departments. Following independence, water resources projects in the Ganga basin were primarily driven by India's developmental and state-building concerns. These large-scale projects generated dispersed benefits, motivating states to cooperate to gain water for irrigation, hydropower, and flood protection while also sharing costs and reducing administrative and technical complexities through interstate bodies. This process fostered interdependencies among the states and between the centre and states, helping to address developmental concerns and manage environmental risks. However, the incentives for maintaining cooperation have been limited to water quantity and distributive aspects, rarely addressing ecological risks like river pollution and aquatic degradation.

From 1990 onwards, river pollution started to gain public attention as well as policy traction. The launch of the Ganga Action Plan in 1990 was an important step towards a gradual and incremental development of India's environmental policies and institutions. In the last few decades, the trend in India's water resources management has been shifting towards quality concerns. The inclusion of Ganga Rejuvenation within the Ministry's mandate and the gradual rise of discussion on issues related to river restoration, conservation, and ecosystem health are indicative of these shifts. These incremental steps have finally culminated in the NGP with NMCG as its executive body with both implementing and regulatory powers.

The NGP, although centrally driven, marks a clear departure from earlier initiatives by recognising states as key drivers and equal stakeholders. Its institutional structure acknowledges the importance of the states for the Programme's endurance, but the core mechanism remains the Centre's financial leverage and state use of funds to enhance infrastructure addressing river pollution, as seen in ETF meetings. Both the Centre and the states have yet to create a plan for sustaining the Programme after the mission concludes. In parallel, the MoJS has launched an initiative for India's long-term water security vision by closely engaging the states. Conference proceedings indicate that states have yet to integrate ecological risks fundamentally into their water resources management strategies.

The discussion on interstate cooperation in this study aims to provide a foundation and an impetus for designing effective incentives to encourage proactive state engagement. This needs to occur at two levels: first, subnational institutionalisation of the NGP, aligning state responses — budgetary, legal, and institutional — with the Programme; and second, renewed collaboration among states in sharing costs to improve the river's aquatic health. Thus, the Ganga basin offers lessons from its past and a pathway for reimagining future interstate cooperation by harnessing those lessons to address the challenges of a rapidly evolving landscape.

POLICY IMPLICATIONS

The research is based on the preliminary findings from the various publicly available data and our interactions with key stakeholders. However, for the preparation of the policy brief, we plan to conduct an extensive consultation at the state and basin level with the following questions of interest as prompts and to discuss and get inputs on the recommendations emerging from the study.

- 1. Are there mechanisms through which states can cooperate with each other in sharing infrastructural costs in river conservation and restoration? What enduring institutional mechanisms could it follow? Are there learnings from the existing interstate river boards/authorities that could facilitate such transformation?
- 2. How can states cooperate for data sharing and standardisation of data sharing protocols?
- 3. How can the ETF/RCA meetings provide more context and be streamlined in bringing states' perspectives and challenges in dealing with river pollution?
- 4. What are the challenges associated with the states in utilising the funds released under NMCG? What are the financial and institutional responses that would be required from the states to sustain the NGP post its mission life? Pertaining to this, what can be the renewed role of NMCG in facilitating and strengthening India's river rejuvenation programme?

REFERENCES

Arnold, D. (2018). The problem of public works: Colonial engineers and urban planning in nineteenth-century India. Modern Asian Studies, 52(4), 1365–1397.

Azhoni, A., Holman, I., & Grabowski, R. C. (2022). Identifying evolving priorities in national river governance from Parliamentary Questions. Water Policy, 24(9), 1414–1433. https://doi.org/10.2166/wp.2022.125

Basu, B. (2022). Comparing colonial water legacies: Flow and stagnation in legal doctrines. Buffalo Environmental Law Journal, 29, 57–89.

Central Water Commission. (2015). Legal Instruments on Rivers in India. Agreements on Inter-State Rivers. (Part 1 & Part 2) (Vol. III).

Central Water Commission. (2015). Legal instruments of rivers in India (Vol. III, Part I). Ministry of Water Resources, River Development & Ganga Rejuvenation, GoI. http://cwc.gov.in/sites/default/files/legalinst-Vol-III(Part1).pdf

Chokkakula, S. (2014). Interstate Water Disputes: Perils and Prospects of Democratisation. Economic and Political Weekly, 49(9), 75–81. http://www.jstor.org/stable/24479179

Chokkakula, S. (2015). The Political Geographies of Interstate Water Disputes in India. University of Washington, Seattle. https://digital.lib.washington.edu/researchworks/items/f5c32e72-feb1-4273-a875-24ad9fd1f565

Chokkakula, S. (2018). Transboundary politics of cooperation: Telugu ganga project, India. Regional Environmental Change. https://doi.org/10.1007/s10113-018-1348-0

Chokkakula, S. (2019). Interstate River Water Governance: Shifting the Focus from Conflict Resolution to Enabling Cooperation. In Policy Challenges 2019–2024: Charting a New Course for India and Navigating Policy Challenges in the 21st Century. Centre for Policy Research. https://cprindia.org/sites/default/files/Policy%20Challenges%202019–2024.pdf

Chokkakula, S., & Prajapati, P. (2021). Whither India's Federal Governance for Long-Term Water Security? In Water Governance and Management in India. https://cprindia.org/bookchapters/whither-indias-federal-governance-for-long-term-water-security/

Dhawan, B. D. (1993). Water Resources of India and Their Utilization. Indian Journal of Public Administration, 39(1), 1–18.

Fischer, M., & Jager, A. (2020). How policy-specific factors influence horizontal cooperation: Designing federal intergovernmental cooperation in Swiss water policy. Policy Studies Journal.

Government of India. (1986). The Environment (Protection) Act, 1986 (Act No. 29 of 1986). Ministry of Environment, Forest and Climate Change. https://legislative.gov.in/sites/default/files/A1986-29.pdf

Government of India. (1956). The States Reorganisation Act, 1956 (Act No. 37 of 1956). Ministry of Home Affairs, Department of States. https://www.mha.gov.in/sites/default/files/2022-08/The%2520State%2520Reorganisation%2520Act%25201956_270614%5B1%5D.pdf

Hardiman, D. (2007). Flooding and flood control in British India. In Frontiers: Space and Time in Geography (pp. 123–140). Oxford University Press.

India-WRIS. (2012). River Basin Atlas of India. Regional Remote Sensing Centre-West, National Remote Sensing Centre, ISRO.

Irrigation Commission. (1972). Report of the Irrigation Commission. Gol.

Iyer, R. R. (2010). Institutional Framework for Interstate River Water Disputes in India. Economic and Political Weekly, 45(9), 53–60.

Jain, V., Mishra, V., & others. (2019). Drought and famine in India, 1870–2016. Geophysical Research Letters, 46(4), 2075–2083. https://doi.org/10.1029/2018GL081477

Le Marquand, D. G. (1977). International rivers: The politics of cooperation. Westwater Research Centre, University of British Columbia.

Milly, P. C. D., Betancourt, J., Falkenmark, M., Hirsch, R. M., Kundzewicz, Z. W., Lettenmaier, D. P., & Stouffer, R. J. (2008). Stationarity Is Dead: Whither Water Management? Science, 319(5863), 573–574. https://doi.org/10.1126/science.1151915

Ministry of Jal Shakti. (2024). Introduction: Organizational history of the department of water resources, river development and Ganga rejuvenation. Government of India. https://master-jalshakti-dowr.digifootprint.gov.in/static/uploads/2024/03/Introductio1.pdf

Mishra, V., et al. (2019). Drought and famine in India, 1870–2016. Geophysical Research Letters, 46(4), 2075–2083. https://doi.org/10.1029/2018GL081477

Mukherjee, S. (2007). Historical development of canal irrigation in the Indo-Gangetic plains. Water History, 1(1), 35–60.

NITI Aayog. (n.d.). Flood management in India: A critical review of works, institutional arrangements and historical developments. GoI. https://www.niti.gov.in/sites/default/files/2021-03/Flood-Report.pdf

Ray, S., & Pullabhotla, H. K. (2023). The changing impact of rural electrification on Indian agriculture. Proceedings of the National Academy of Sciences, 120(45), e2305489120. https://doi.org/10.1073/pnas.2305489120

Sadoff, C. W., & Grey, D. (2005). Cooperation on international rivers: A continuum for securing and sharing benefits. Water International, 30(4), 420–427. https://doi.

ANNEXURE A:

Analysis of 47 cooperative instances in the Ganga Basin with thematic use and Spatial coordinates

SPATIAL COORDINATES		LONGITUDE	78.23	81.29	60'08	80'08	LONGITUDE	77.4	77.43	77.58	77.09	77.58
SPATIAL C		LATITUDE	24.76	24.19	24.84	24.84	LATITUDE	30.22	27.95	30.31	29.85	30.31
		INSTITUTIONAL	≨	½	Special Purpose Vehkle (SPV) called Ken-Betwa Link Project Authority (RBLA) to be set up Implementation of Project.	Special Purpose Vehicle, Le., Ken-Betwa Link Project Authority (BSLPA).	INSTITUTIONAL	¥	MA	NA	NA	M
		POWER GENERATION	ž	ş	Generate 103 S NW of hydropower and 27 MW c Solar power utilising about 4,849 A MOA of water.	¥	POWER GENERATION	A	NA	NA	NA	A
		INTER-LINKING/ INDUSTRIAL	¥	М	Ken-Betva Interlinking.	Ken-Betwa Interlinking.	INTER-LINKING/INDUSTRIAL USE	ă	NA	NA	NA	Ä
IMPLEMENTATION	THEMATIC USE	WATER SUPPLY/ SHARE	ä	Palsun Project: 1462 m.c.ft. of water reserved for upstream use in M.P., and the balance will be used by U.P.	Drining water supply to a population of about C2 lakes. Proposed water transfer to Betwa Basin 2.2.7 TMC Ecological Requirments D/c of dan 11.23 PMC.	Supply drinking water to 62 lakh people. Water Sharing (in Normal Year): MP: shall utilise a total of 2350 MP: shall utilise a total of 2350 MP: Water Sharing (in Normal Year): MP: Water Sharing (in Normal Year	WATER SUPPLY/ SHARING	British Canal Officer Discretion	NA	NA	Water supply rates would be identical in both the states.	Total river discharge is in excess of 10000 cusess the Punjab and the UP will have the right to utilize the excess over 10900 cuses in the ratio of 211.
		INFRASTRUCTURAL	Greater Gangua Dam We completed the investigation with certal Marker & Kower Commission assistance. Commission Laliguar Dam M will construct an extension of the caral system in their area.	Raighes Project: To be started as soon as possible con as possible con as possible con as possible con an advantage of the sand from the flank chand from the sand from th	¥	UP shall be free to create addrtonal stooges in its own territory downstream of Baringhory Ownstream of Baringhory VIVI was sore monotoon wafer as per its requirement during non monotoon.	INFRASTRUCTURAL	A A	NA	NA	NA	¥.
		созт	Cost will be equally divided in proportion to the benefits. Lalityour Damic Cost of the cannal system will be bonne by (NO)	Rajghat: I.C.: by MP. & the rest sponsored by Vehord Barnfor by a Middle East Country of Middle East Country of Country o	Cost of % 44,605 crore and shall be completed in 8 years.	Estimated cost of ¶ 44,605 crore (year 2002-12 price level) with a central Support of ₹ 99,317 crore.	COST	Butana Distributary constructed at the cost of the British Government	Bharapur Darbar agrees to bear the coxt of constructing an Escape Channel from Nandgaon Distributary, Agr a Caral to the Bharapuru State boundary, Induling in Recessary channel and works to the far and works to Dig and de	Reparing Cost given by Punjab.	Cost Sharing - Amount payable each year by the Durbar to Govt will be based on the income derived from the Sunds of Sub-Banch system in Punjab frantory and will be in proportion to the share discharge.	Cost Sharing to be proportionate in the ratio of total discharge in cused days run in two canais during the current year. Maintenance Cost - Punjab Govt.
		IRRIGATION	ž	\$	The project provides an annual irrgation of 10.62 lish ha. (considering CCA of 5.04 lash ha).	olyect shall provide irrigation to 10.52 labs hectares in the premaring drought provide are an and water starved regions in historypus, hums and tralmagen historypus handon and hannjoi pradesh. Mahooba and hansi of Uttar	IRRIGATION	Western Yamuna Canal Major Irrigation Project benefiting districts of Bilward, Saharangur, Muzaffarnagar, Baghpat, Ilind, Yamunanagar, Sonipat, Rohtak, Panipat, Kurukdare, Karnal, Majiar, Hisar 436 tha irrigation potential	NA	NA	NA	NA
		BENEHT SHARING	Raighat Dam will have 62 TMC live storage (16 TMC dead storage). Its storage, severage 79 TMC or countered downstream uses in the and Mr. remaining users as lared between the and UP may use 9 TMC for downstream and Bhander Canal, with excess use requiring particle and approve which the permanent (which language to lona doors Mr. up to 2 TMC or for the counter of the superior of t	¥	National Water Development Agency (NWDA) Conducted a study on benefit sharing. Gooss Water are sailed: 12.52 FJMC kM requirement (upstream of Daudhan Dam): 80.03 FJMC Regeneration capacity; 5.55 FJMC flet Water Balance available: 15.41.2 FJMC froat lequirement (MIP: 59.58 FJMC (including DS): use: 48.55 FJMC ent outer use: 3.25 FJMC, consists use: 85.55 FJMC flet requirement of UP: 60.04 FJMC (including DS) and domestic use). The benefit-cost ratio and BIRR have been worked out as 15.11 and 11.26 %.	The tripertite MOU signed on 25th Aug 2005 shall be affected to More meaving 2566 MOX for upstream and received to More meaving 2566 MOX for upstream uses in APP in Ken basin Uy of Daudhand am, and accounting for mendatory reflease for environment and networking for mendatory reflease for environment and networking for mendatory reflease for environment and network to Basingsuper risks by well-(VM) shall be dutiesed by the states of Moy more University of Salary and Pelon In Ken and Bewo G. Basins. The committed releases and any defloit from Daughan reservor during the non-monosome protei (Nov. to Mary): WR: 1554 MCM (1256).	BENEFIT SHARING	Water course heads sheen out of the Buttana Distributary shall be constructed at the cost of the British Government. (Dedingur Barrage)	¥	Repairing the damage done by the floods of 1924.	For thank supply, the respective shares of the Gost and the Durbar will be calculated on the basis of the ratio of the sanctioned total had capacities of the Government and Durbar channels, including direct outlets from the Sundar Sub-Branch.	Western Junns canal and Eastern Junns canal water sharing between UP & Punjab.
ANGEMENTS		MAJOR HIGHLIGHTS			Lower Orr Dan Lower Orr Dan Sweenhoed burnge Skrad burnge Skrad burnge Skrad burnge		МАЈОК НІБНЦБНТЅ					
COOPERATIVE ARRANGEMENTS		PARTIES	Uttar Pradesh (UP) Madhya Pradesh (NP)		Uttar Pradesh (UP)	Union Government	PARTIES	British Government The State of Jind	Rulers of Bharatpur State Government of the United Province	Punjab United Provinces	East Punjab The Jind Government	Punjab (PB) Uttar Pradesh (UP)
		AGREEMENT	Agreement on some trigation projects in Bundelshand.	Minutes of Meeting of the Chief Ministers of the And Un regarding the following projects: (I) Raginat project (I) Basisan (poiet, (II) Raginat Canal, (Iv) Tanit (A) Bansagar project, (Ai) Bhander canal	Memorandum of undestanding (MoU) on Ken-Betwa Link Project	Memorandum of Agreement (Moca) amongst the States on the implementation of the Kenebetwa Link Project (RIR.P)	AGREEMENT	Amen ded terms of the agreement between the British Government and the State of Info for egulating the supply of water for irrigation from the Western Jumna canal.	Agreement between rulers of Bharatpur state and government of 1 Burled Province in August, 1305 regarding Nandgaon die scape and further rules dated 9th March, 1909 for running the dig escape for running the dig escape	Agreement between the Punjab and United Provinces Governments regarding supplies to the Eastern Jurna canal.	Working agreement between the Government of East Punjab and the Jind Government for khaif supply for areas in Jind territory from the Sundar sub-branch of the Western Aurma canal extension scheme.	Draft agreement between the Punjab and Uttar Pradesh Gorts. regarding distribution of supplies of river Yamuna at Tajewala, between vestern Jurma canal and Esstem Jurma canal and psportonment of expenditure on Tajewala headorts! and related works.
		YEAR	278	7761	2005	2021	YEAR	1892	1905	1925	1943	1954
		KEN-BETWA-SONE	KBS1	KBSZ	KBS3	K6S4	YAMUNA	ŗ	7.5	Y3	74	Y5

77.58	77.78	77.44	77.58	77.58	77.58	77.58	97.77	LONGITUDE	79.86	78.44	78.44	78.44	78.2
30.31	30.64	27.89	30.31	30.31	30.31	30.31	30.51	LATITUDE	24.71	26.08	26.08	26.08	24.76
NA	Proposals accepted in the agreement for Dan should be constructed on the Tons River and Girl River.	reactor channel taking off from Aring Darkbutany along with its appurtenant vorks including remodeling of Aring Darky in its first mile and strengthening of Regulator floor in Agra will be maintained by the infigi	A technical Committee headed by the Membe (1984) of the Central Water & Dower Commission and the Chief Engineers of the two States was appointed to examine and finalise the relative economics of finalise the relative economics of	Capacity and the type of Carrier shall be decided by Delhi Administration, in consultation with Haryana.	Upper Yamuna River Board (UYRB) was created.	Haryana operate and maintain the Hathnikund Barrage.	A A	INSTITUTIONAL	¥	MP Irrigation Branch shall maintain and operate the Bhander Canal System.	NA.	N.	Tripartite Control Board for the speedy, smooth and efficient execution of the various interstate projects of UP and MP. Sanding Committee will be constituted for taking management decisions as may be delegated by the Board.
AA	NA	AA	MA	NA	AA	NA	¥	POWER GENERATION	Matatila Dam - generates about 45 MW of power.	NA	NA	NA	NA
V.	NA	ž.	AA	NA	NA	WA	A A	INTER-LINKING/ INDUSTRIAL USE	N N	NA	NA	A	NA
NA	NA	in monsoon period, UP will supply surplus Yanuna River vuster to RJ, 300 Cusec.	AN	Carrier shall be fully dedicated to Delhi's water supply requirements.	1. HR - 5.730 BGM. 2. UP - 4.022 BGM. 3. N - 1.113 BGM. 4. HP - 0.378 BGM. 5. Delh - 0.724 BGM.	NA	368 cusecs (Nov-Feb) 268 cusecs (Mar-Jun)	WATER SUPPLY	Ä	NA	Equitable allocation	M.P. and U.P. agreed that it should be 6.5 TMC and on ad-hoc basis, for this rable seaon only. Weekly water account may be maintained by M.P. & RJ.	Madhya Pradesh will use its full share of 26.5 TMC from Rajghat.
¥	NA	\$	Haryana to construct the Tajewala barrage and UP to construct the Okhla barrage	Construction of this Carrier shall be carried outby Haryana.	NA	Haryana shall construct Hethnikund Barrage.	A	INFRASTRUCTURAL	Matatila Dam	NA	Rangwan Dan Bhander Canal (Matatilia Dam Canal) Jamri Dam	NA	Raighat Dam
Rajasthan requested a Feeder Canal, Punjah proposed Gurgoron Canal Project, designed for a discharge of 1.105 curses to be run when supplies at Oblia are available over and above the existing equivement of the Agra Canal.	Cost Sharing - according to the benefits recieved by the state.	10: Gort will be an the expenditure for annual manual minerance and regain induling supervision of the freedor in U.P. upto the annual of Ra. 7,000/- Asio, Rs. 2000 for the clearance of Agic Canal shall be placed by the lightnian Government at the disposal of the fully mades froot, in the month of Agic Revey year.	Cost of the Tajewals barrage would be shared in the ratio of 2.1 by Haryana and Utter Praciesh. Cost of the Okhia barrage is to be shared in the ratio of the discharges required to be drawn by each State.	Entire cost of this Carrier shall be borne by the National Capital Territory of Pells. After its construction, Hayana shall maintain and operate this Carrier on behalf of Dehl, the annual charges being paid by Dehls.	NA	Cost of the Barrage be initially financed by Haryana. Cost of Barrage including the cost of Head Regulators shall be shared by He, UP, RI & NCT of Delhi.	ź	1502	Ā	The actual cost of the maintenance and operation of the canal system plus the establishment charges shall be limited to Re.4/- per acre of the area actually irrigated in a particular year.	Rangwan Dam: 19:36. Jamin Dam: 450:2200, with MP bearing costs of outsets structures and canal systems within its ter front, and UP covering the remaining expenses based on usage and infrastructure location.	A	Ā
NA	NA	\$	A	NA	NA	NA	NA	IRRIGATION	MP utilizes for Kharif crops upto 31st October upto 2 TM.C. and the balance storage as available on 1st November will be chided between UP and MP in the ratio of 36:15.	NA	NA	NA	AA
Due to the increased capacity of the Western Yamana Canal by Pupila, a 2000 cases, the supplier as destituted in the ratio of 8,000 cases, the supplier as destituted in the ratio of 800 cases for the pupil 2,000 cases for try. There should be now with dawness into either canal shalling of at Talewale below Othis, after meeting the requirements of the Age Tanal. An injuly lowants the suppliers of the March 20,000 cases on a full capacity, which to opposed by others.	Benefits on account of the Kidaus Dam will be shured between the States. The share will be in respect of water and in respect of power produced at the Kidaus Dam site.	UP has agreed to supply surplus Yamuna Reer water to the Rajacidan State frought het Ager Casia let morecom period for being sufficed for frieting to Principal and of Bharaspur Dibritice, Rajacidan	The technical committee has come to the conclusion that it would be advisable to construct a new barrage at Tajeweals.	Dehis will continue to have a share in the equality of Dehis Branch as here to before and will be feet to use the Dehis Branch and the new currier together in a suitable manner in consultation with harvans within the overeit allocation of Dehis Siper MOU.	Basis States agree on allocation of the utilitable water resource of the Yamana association are available, which will be required by URB if its surplus availability, will be distributed amongst the States in proportion to their allocations.	Construction of Hathinkurd barrage on river Yamuna.	He will supply its unstilland Vennina water to Delhi with seasonal alkolinor of 188 cases of the Cherch all and 586 cases (Mexi-uni), potentially rising to 21 cases annually inter- upte team stoops, while Delhi blass 1950 of ferminal Dan's power costs, regulated by the Internation of the Internation cooperation needed for canal conveyance.	BENEFIT SHARING	The intensity of irrigation in the new areas to be brought under irrigation - 33% while it will be 45% for such areas of U.P. as are irrigated by the existing Belwa Chall System of that state.	The MP, Irrigation Branch, shall or edit the net revenue from the Bhander Chanl System to the UP Government, Irrigation Department, after deducting the maintenance and operational charges.	¥	The demand of Madhya Pradesh for Bhander Canal for the Rabi Season 1979-74 was putforward as 7.3 TMC, against 5.3 TMC worked out by U.P.	Madhya Padesh will use its full share of water from Raghat Dam. The height of Raghat from should be decided by the Central Water & Power Commission.
	Western Yamuna Canal Z. Tajewala S. Eastern Junna canal Weper Yamuna River Board S. Hehrhridund barnaes.	i						MAJOR HIGHLIGHTS			1. Betwa Canal.	2. Mattata Dam. 3. Rajghat Dam. 4. Bhander Canal. 5. Rangwan Dam 6. Jamni Dam	
Punjab (PB) Rajasthan (RJ) Uttær Pradesh (UP)	Himachal Pradesh (HP) Delhi (DL) Punjab (PB) Rajasthan (RJ) Uttar Pradesh (UP)	Punjab (PB) Rajasthan (RJ) Uttær Pradesh (UP)	Uttær Pradesh (UP) Haryana (HR)	Haryana (HR) NCT Delhi	Uttær Pradesh (UP) Haryana (HR) Rajasthan (RJ) NCT Delhi (DL) Himachal Pradesh (HP)	Uttar Pradesh (UP) Haryana (HR) Rajasthan (RJ) NCT Delhi (DL)	NCT of Delhi (DL) Himachal Pradesh (HP)	PARTIES	Uttar Pradesh (UP), Madhya Bharat & Vindhya Pradesh			Uttar Pradesh (UP) Madhya Pradesh (MP)	
Draft proceedings of the inter-state meeting between the Chief Engineers of the Punjab, Ustar Prodeb, and Balbstham regarding the distribution of waters of the Jumna river held in the Central Water & Power Commission's room.	Summay record of the decision taken at Inter-state meeting among the governments of Himachal Pradesh, Uttar Pradesh, Punjah, Dehi and Rajasthan regarding Yamuna water development.	Dr aft agreement for supply of 300 cuescs of water to Bajasthan state through Bhar agus freed channel of flashing from mile 2st sight bank of Ang Gierbuary of flashing from Ange Canal at mile 65 leight bank.	Agreement regarding Tejewala and Okhla barrage.	Memorandum of Understanding (MoU) regarding the construction of an additional parallel water carrier system from Munak head exclusively for carrying water for Delhi.	Memorandum of undestanding (MoU)) regarding allocation of surface flow of Yamuna signed by Chief Ministers of basin States.	Agreement regarding construction of Hathnikund barage on river Yamuna	Memorandum of Understanding (MoU) between Himachal Pradesh and NCT of Debi for the supply of water on the 20th day of December, 2019	AGREEMENT	Agreement regarding Matatila and Rangawan Projects, between Uttar Pradesh, Madhya Bharat and Vindhya Pradesh.	Agreement between UP and MP regarding Bhander canal system.	Agreement regarding Projects in Bundelkhand: Rangwan Dam, Bhander Canal and Jamni Dam	Summary record of discussions of the meeting held in CWPC Committee Room, Bilaner House, New Delhi, regarding supplies to Bhander canal-fabl season of 1973-74.	Agreement between the governments of UP and MR about the Rajghat project.
1955	1963	1964	1974	1993	1994	1994	2019	YEAR	1953	1965	1962	1973	1973
9A	4	\$A	64	V10	V11	Y12	Y13	BETWA	18	B2	83	#B	88

78.23		LONGITUDE	75.83	75.55	75.55	75.55	75.55	75.58	75.58	75.58	75.58
24.76		LATITUDE	25.18	24.7	24.7	24.7	24.7	24.92	24.7	24.7	24.7
Betwa River Board is created by Central Govt.		INSTITUTIONAL	NA	Formation of Chambal Control Board	ž	¥	N	NA	Water Regulation Committee	Constitution of Madhya Pradesh - Rajasthan Inter-State (Intigation & Power) Control Board.	The Field Agency for Water Regulation (FAWR) was constituted under the Inter-State Control Board.
Ā		POWER GENERATION	onstruction of bridges across the are completed to be worked out in	M	ž	ź	A	NA	Ā	Ā	ş
NA		INTER-LINKING/ INDUSTRIAL USE	truction town, layout of the roads, c ising of about 15,000 labourers, etc. xmonths.	NA	ž	ž	NA	NA	NA	NA	A A
NA		WATER SUPPLY	tions, power plant, layout of the cons of the colony and the works area, hou detail within si	M	¥	\$	V V	44	Weeky water account may be maintained by M.P. & Rajasthan.	\$	NA
Reservoir at Rajghat would be constructed		INFRASTRUCTURAL USE	investigations regy ding communications, power plant, layout of the construction town, layout of the roads, construction of bridges across the Chambal, Saritation and water supply of the colony and the works area. housing of about 15,000 labourers, etc. are completed to be worked out in detail within six months.	\$	ş	\$	V.	NA	The government of M.P. may post a small cell headed by an executive engineer at Krota at the cost to maintain the weekly water account.	\$	NA
NA		cosT	NA	¥	Sent to State Gont for approval.	Approved as per the proposal.	The Board agreed to submit the certified accounts of common works of the Chambal Project to the Board's offices to that the Board may be apprised of the factual position from time to time.	Cost shared in the ratio of 50:50.	≨	\$	NA.
MA		IRRIGATION	NA	Agricultural Experimental Farms for instructing roots in the use of irrigation fadilities were established in each State.	ž	ź	¥.	NA	NA	Ā	\$
The Central Government will establish a board under its control to regulate and develop the inter-state Betwa River control to regulate and River Valley.		BENEFIT SHARING	Madhya Bharat Union to provide funds to undertake investigation on multipur pose development schemes on the Chambal River.	The project report and estimates should be revised to endude the Rane Prates Sager, Dam from the Project. It was seen that the CAMP.C. would furnish a note on the costs to be shared by each state. In sharing of the cost of transmission lines etc. would also be taken into account.	() Gandhi Sagar Dam cost (Rs. 1350.25 labbh) Abred dequally, II) cosh Barnge cost (Rs. 352.55 labbh) Abred dequally, III) other Mand destructures oct (Rs. 124.44 labbe; [01]) Right share, Canal (Big Sagar (Rs. 124.44 labbe; [01]) Right share, Canal (Big Cost Sare et al. 56.00 labbt; [01]) No fight share, Canal (Big Cost Sare et al. 56.00 labbt; [01]) No fight share (Canal (Big Cost Sare et al. 56.00 labbt; [01]) No fight share (Canal (Big Cost Sare et al. 56.00 labbt; [01]) No fight share (Canal (Big Cost Sare et al. 56.00 labbt; [01]) No fight share (Canal (Big Cost Sare et al. 56.00 labbt; [01]) No fight share (Canal (Big Cost Sare et al. 56.00 labbt; [02]) No fight share (Sare et al. 56.00 labbt; [03]) No fight share (Sare et al. 56.00 labbt; [03]) No fight share (Sare et al. 56.00 labbt; [03]) No fight share (Sare et al. 56.00 labbt; [03]) No fight share (Sare et al. 56.00 labbt; [03]) No fight share (Sare et al. 56.00 labbt; [03]) No fight share (Sare et al. 56.00 labbt; [03]) No fight share (Sare et al. 56.00 labbt; [03])	Reaffirmed the distribution agreed in the Meeting (1560) on common works on Chamber Projects. If The water utilised in generating power is to be sold by the fregions storc for the Projects (2000 the sold by the fregion storc for the Projects (2000 the sold by the fregion storc for the Projects (2000 the State Cont to Ming the Income of about freet by the State Cont to Ming the Income of about freet by the State Cont to Ming the Income of about freet by the State Cont to Ming the Income of about freet by the State Cont to Ming the Income on 1250 of the total generating capacity When the State Ming the State of State generating capacity from the Burth year, and full generating capacity from the Burth year, and full generating capacity from the Burth year and convention. In The R Lifore, Another Economics In regard to the the share of the costs to be changed to the Irrigation sector and aloo filting the rate of supply of water.	Matter of cost allocation for the Chambal Project between Rajacthan and Madfley Pradesh is under active consideration.	I) The cost of hans Pratap, Sagar Dam and Power station at Koto Dammer we be said on the ratio of S200. I) Regarding the allocation of expenditure on Dam and again trens froots of the allocation of expenditure on Dam and again trens froots of false allocation of expenditure on the respectation and power, the Bood decided that this may be first discussed between the respectantities of the two Szete Governments and the matter brought before the Board separately for condensation.	ž	N	ž
		MAJOR HIGHLIGHTS				1. Rana Patato Sage Dan 2. Kosto Dan 3. Ganfili Sager Dan and Power Station. 4. Kotalh Barrage					
		PARTIES	Rajasthan (RJ) Madhya Bharat Union (Malwa Union)			Madhya Pradesh (MP)	Rajasthan (RJ)				
Establishment of a board for the creation of a reservoir at slaghst by construction, on behalf of the Government of the Rad Up, of a dam on the Betwa river at Rajghata and for the regulation of such reservoir.		AGREEMENT	Agreement between Rajasthan and Madhya Bharat Union held in the Manikbagh Annexe, indore	Summary Record of decisions arrived at in the meeting held in the Planning Commission regarding the Chambal Project	Proceeding of the Meeting held to discuss the unestion of allocation of odds of common versit of the Chamba Moject between the States of Madnys Practer and Rajastham	The decision of Government of MP on the allocation of the cost of common works on Chambal Project	The decision of the Chambal Control Board on the allocation of the cost of common works on the Chambal Project along with a note on item No.21 of the Second Supplementary Agenda	Extract from the summary record of the decision taken by the Chambal Control Board at its skrky-skth meeting held at New Defin.	Decisions arrived at inter-state control board meeting regarding Water regulation committee in the command of Chambal Project	Constitution of Madhya Pradesh - Rajasthan Inter-State (irrigation & Power) Control Board	Decision arrived at intensitate control board hereing regarding constitution of the field agency for water regulator (FAMP) to ensure implementation of the decision of the control for the standing control for the standing of the control for regulation of releases from the reservoir (FAMP) as mange in the canal system expecially the common system expectally.
1976		YEAR	1948	1955	1960	1961	1963	1966	1973	1973	1981
98		CHAMBAL	n	α	σ	2	ຶ	8	D	8	9
	L										


	LONGITUDE	83.01	78.37	82.84	81.29	81.31	78.36	81.71	83.07	8411
	LATITUDE	24.2	25.1	24.14	24.19	24.52	23.05	24.41	24.19	23.84
	INSTITUTIONAL U.P. Government shall provide	Tadilities, to the extent feasible, for uninterrupted use of the Rihand as an inland waterway for boating and transport purposes.	Formation of a committee to settle the cost of power generation compressed of Polivairo, Central Valeds and Power Commission and the power Commission and the power Member of the Central Waster and Power Commission.	AA	ž	Bansagar Control Board was set up vide Government of Inda, Ministry of Agriculture and Irrigation Resolution No. 8/17/74. DWH. Ideath et 3.0th January, 1976. It was amended vide Resolution No. 18/17/74. DWH. dated the 2.8th March 1.990.	Chamma, UPSE accepted the offer of MFEB in as much as rates are constructed for two periods in the year, but did not agree to supply addronal 3DS over and above MFS state in sladelic energy at the aforesaid rates.	Constitution of the field agency for water regulation (FAWR). Standing Counties to work out the modalities of the proposed agency for field level implementation on priority.	NA	CVC would be the responsible authority in the construction of the Baradin Dam.
	POWER GENERATION	Ā	Supply of power to Madhya Pradesh from the Rhand and the Mataliat Power strations to cared in U.P. State Electricity Board to make available to the MP Electricity Board to make available to the MP Electricity Board con energy. The other properties of one energy and the properties of one energy content of yellow the properties of the p	₹	ž	¥	UP agreed to compensate NP for C the difference in power not supplied between LLDS ST to	≨	Bandhav Thermal Power Station: Intial capacity - 2 x 500 MW ultimate capacity - 4 x 500 MW (2000 MW). Mand Thermal Power Station: Initial capacity - 2 x 21C MW ultimate capacity - 6 x 210 MW (1256 MW).	\$
	INTER-LINKING/INDUSTRIAL USE	USVP shall have the right to pump wave for industrial uses but no effluent from any industry shall be discharged into the Rihand.	Ā	NA	Ą	NA	HA	AA	NA	Ā
	WATER SUPPLY/ SHARE	NA	Ä	MA	ă	NA	M	М	A	¥
	INFRASTRUCTURAL	NA	A	¥	Benzage Dann	4	44	Kota Barrage	Bandhav Thermal Power Station in the Sidihi Döstrict. Mand Thermal Power Station in the Rajgarh District.	Baradih dam may be constructed by Bihar to utilize its share of 0.43 MAF. Bihar and M.P. agree to the construction of a dam near village Anwar as proposed by U.P. for utilizing 0.15 MAF.
	UP: Compensation for the submerged lands, houses, forests	and public ways, etc. In addition, compensate USVP. for the recettlement of dispossessed people on the same scale as it would cost the UP to resettle dispossessed people in their own area.	Rith and Power Station to MP: (coor opporture - Station to MP: (coor opporture - Station SV) up to a colling of SV) the subable energy including a suchage for recessory. Materials Power station to MP: Power station to	Detailed studies are to be made by a team of Eightees from Bhaz and Utar Predes States to draw up detailed recommendations, including financial sepects, for consideration by the Govts of Bhaz and Uttar Fradesh.	The cost of from little is to be shared in the series of Zatta encought My UP, Bit. Based on the plant of water allocated to the states.	¥	MP offered to pay at the rate of 5.5 palack/Whn for energy supplied from Mastals during the four monson months and at the rate of 5.5 palac pay 4 Whit for the other of months of the real audictive to the contribution for the real audictive to the contribution factors are provided to the real pay of the pay and provided to the pay and provid	\$	The costs and benefits of these two projects withe strated by the two states equally and power will be shared without regard to any power cut prevailing in Madhyra Pradesh.	Ą
	IRIGATION	USVP shall have the right to pump I water from the lake for irrigation.	¥	₹	MRF. Storage of ZO MAR would be for first use. They would be for a total of ZD MAR, at their up to a total of ZD MAR, at their up to a total of ZD MAR. at their site for current and future implication. MP will also use 1.0 MAR. in the area uppraison of Bunasapir for their properties of ZD MAR. In the area uppraison of ZD MAR. UP will be a LES MAR. Of Some waters for LES MAR. Of Some waters for their properties of SD MAR. OF AD MARK TO	¥	\$	\$	¥	\$
	BENEFIT SHARING For eshore land within the USVP, shall be available for cultivation to USVP.	The U.P. Gort would undersake a planted development of the lake for fish culture, and the net profit account the lake for fish culture, and the net profit account therefrom shall be shared between the two states in proportion to the volume of territories.	A settlement rigarding the supply of power to Mushing Puckels from the Brithand and the Mushing Amentalis Power stations Packels from the Brithand and the Mushing Amentalis Power school of the meeting of the Central Zonal Council held at Naming A. Committee was appointed by the Coliman of the Central Zonal Council Comprising Mr. Scholer as Chairman, the Company Alvase and Power Commission Filts N. Sa Man Packer and Coliman of the Central Power Commission Filts N. Sa Man Server Commission Filts N. Sa Man Per Commission Filts N. Sa Man Per Commission Filts N. Sa Man Server Commission Filts N. Sa Man Server Commission Filts N. Sa Man Per	Bhar request that 0.3 m.a.ft. of the Rhand storage may be reserved for them for additional waters for frigation under served for the foreign and the served for the foreign and the served for the foreign in October.	The proportion of cut of increase would be \$.252.75.1.25 for Mediny Pradesh, you will be "a will be proportion of cut of increase," and these Pradesh, UP will use Sone waters for irrigation. The allocation of water from the Sone River agreed to would be for little #0.775 m.a.ft. while it is 2.55 m.a.ft for Melle it is 2.55 m.a.ft for Melle it is 2.55 m.a.ft for the ALP and ALP an	For economical and early execution of the Bansagar Project in Madhips readshich clouding connected works, the Control Board to be in overall charge of the project including its bechnical and financial aspects. The area worked or construction that be carried out under the direction of the Control Board by the child eighest concerned of the Naching Pradeal Government.	ă	ă	To implement the establishment of joint covership thermal power stations in pursuance of the policy of the Govt, of india to establish sout stations and make, in the largest out stations and stations and make in the largest interests of the stock of the Child Michaetra of in. Madhya Pardella and Gujast aspect to establish jointly the following thermal power stations in the state of Madhya Pardella mad Gujast aspect to establish jointly the following thermal power stations in the state of Madhya Pardella.	The share of Binar in Contra winters a Burstills shalles Q. A. Mod. The a share M. A. Da also B. Charles A. Mod. Ston Berstell stam. Also and Burstills and Brandla of G.S. A. Mod. Shares Burstills and M.A.—L. D. Border. Mondelfastanding that the flewer State Gorst, and feet to use their share of Kanhaw waters in the best manner they like.
	MAJOR HIGHLIGHTS				1. Kota Barrage. 2. Bihand Power Station. 3. Matabals Power Station. 4. Riband Hold opower Toler. 5. Barrage Dum. 6. Barrage Dum. 6. Barrage Toler. 7. Polect. 9. Polect.				1. Bandhav Thermal Power Station. Station.	Baradih dam
		United States of Vindhya Pradesh (USVP) Uttar Pradesh (UP)	Utar Pradesh (JP) Madhya Pradesh (MP)	Uttar Pradesh (UP) Bihar (BR)	Madhya Pradesh (MP) Uttar Pradesh (UP) Bihar (BR)	Madhya Pradesh (MP)		Madhya Pradesh (MP)	Gujrat (GJ) Madhya Pradesh (MP)	Uttar Pradesh (UP) Madhya Pradesh (MP)
	AGREEMENT	Agreement between the Uttar Pradesh and the United States of Vindhya Pradesh relating to the Rihand Dam Project.	Minutes of the meeting held at New Delhi on Zuld. & 24 September 1994. On (I) Stoply of Power from Rhand to (II) Stoply of Power from Rhandlis to (III) Stoply of Power from Matallia to Mr. Mr. Ann. And (III) Sheberio of Water From Rhand Carbinetto of Metine From Rhand Carbinetto of Metine Rhand R	Agreement dated 16th September, 1973 between the Governments of Bihar and Urtar Pradesh on Rihand Reservoir	Agreement on Bansagar project	Resolution for the constitution of Bansagar Control Board	Minutes of the meeting held in the count of kember (hydro-Esecutio, Central Settors Lathority with the respectations of the settors and Mandha hands sate Best single Beads to garding settlement of custaming stous between Urta Practicle and Maniph Practich for power supplies from Rilland and Mandha Practic Maniph Practic and Maniph Practic power supplies from Rilland and Mandha Practic Practic and Maniph Practic	Comments of the Government of Madry's Pradesh (fregisten Madry's Pradesh (fregisten Oppartments the LF. Governments of an onstruction of new schemes for consumptive use of water by MR. In catchment area of water by MR.	Establishment of joint ownership thermal power stations of Bandhaw Thermal power Station in the Sidhin District Power Station in the Sidhi Station in the Rajgarh District	Agreement on sharing of Kanhar waters.
	YEAR	1948	1964	1973	1973	1976	1976	1981	1981	1982
	SONE	15	25	æ	3.	s	8	55	8	8
L					l .	<u> </u>			<u> </u>	

83.01	83.01	10-68	LONGITUDE	83.6	LONGITUDE	86.48	LONGITUDE	83.29
24.2	24.2	34.2	LATITUDE	27.43	LATITUDE	24.03	LATITUDE	24.97
Joint Monitoring Committee (JMK)	Sub-Committee: Chairmanshi pol Chair Espignee (BANQ), CVC, with offerest (BANQ), CVC, with offerest from timigation/water learners of social control properties of the committee of social control properties of the committee to social control properties to social control properties to social control con	ž	INSTITUTIONAL	MA	INSTITUTIONAL	MA	INSTITUTIONAL	A A
North Koel Reservok Project: The Intzaked capachty of yower generation at the Dan shall be 24 MW (2 X 12 MW) - shared in the Inverse proportion to the ratio of	ž	For Hydes Power Poeentals of Rhand beam in Madhing in Pradesh, UP agreed. (For Power Generation 10.367)	POWER GENERATION	¥	POWER GENERATION	¥	POWER GENERATION	\$
¥	Bhar has reled the issue of compensation from Banaga reservoir a place of commensation from Banaga reservoir a place of commentive the management of the place of commentive for the place of the place	¥	INTER-LINKING/INDUSTRIAL USE	UP will ensure to draft at 10.0 Class of the state border. Also, make efforts to gradually increase discharge to 5000 cuser. Sono custon of the state of the state out of its share under the Wiczana system to thermal power class in 88.	INTER-LINKING/INDUSTRIAL USE	ИА	INTER-LINKING/INDUSTRIAL USE	ž
Bateshwarsthan Pump Canal Scheme: 78 cuses 8/w JH & BH.	A	¥	WATER SUPPLY/ SHARE	¥	WATER SUPPLY/ SHARE	MA	WATER SUPPLY/ SHARE	ź
North Koel Reservoir Project & Batnes Reservoir Projects: Construction of Nam, Barrage & Detribution	A A	ž	INFRASTRUCTURAL	Western Gandak Main Canal & Thermal Power Plans from WGMC (called Ssram Main Canal in Bibar) of Bibar.	INFRASTRUCTURAL	Musakhand Dam	INFRASTRUCTURAL	¥
Cost for everything will be shared in the proportion of the benefits derived by the respective States on CCA consider alson.	¥	¥	COST	A5	соѕт	Cost shared equally between UP and BR.	соѕт	DOT will been the cost of acquisition and chabilitation for lands which in Bear and out of the Bear and not state of the Cost. West Bears will be bear and the cost. West Beargaw will bear the cost for areas submerged in Bear, where Beargaw will bear the cost for areas submerged by the displant of meta submerged by the displant of the share and the submerged by the displant of the share and the submerged by the displant of the submerged by the subme
North Koel Reservoir Project 987 MCM (0.52 MAF) available water shall be abrained in proportion to the frigation and M8I benefits derived. Batten Reservoir Project. 65.14 MCM (10.52 XMAF) available water shall be shared in proportion to the irrigation benefits derived.	The subcommittee found Binar's demand of increased integration by modifying the operation pattern of Binard physiopores project as not leastle for an increased integration of the integration of the state of the integration of water by the integration and water by the integration and water by the integration without according for the distribution transition and the properties of the project of	For integrion Potential of Bhand bain in Mahinya Proteits, UP agreed. (For Integrion - 1,031 maf).	IRRIGATION	¥	IRRIGATION	Karamansas flows at Latifaths are shared between titler and the ar shared between titler and the shared and 30.70 during Rabb, with Bithar receiving LST Mich in RAbb count of a Kharff and 0.31 Mich in Rabb count of a LST KH. of 13.25 ThC, allocations will be proport donally reduced.	IRRIGATION	¥.
North Moel Reservoir Project & Batane Reservoir Project Both governants, agree in principe that the excess or effects based on 10 clayl version and relationship to the two States in proportion their relations and the morning as fandarish (Mal) benefits defined by moring of two Post Statemer 75 cuests where pumped from the Cases through this scheme shall be shared between the States of Batan and Inharkhardin in proportion to the registion benefits derived.	U.P. & Bihar to meet perfodicable every two months to analyse the refuses patient vice-vie the J.O.C recommendations from Rhand dam and try to solve the factor structures from Rhand dam and try to solve the factor structures from Rhand dam and try to solve the factor solves blance ally.	Makhya Pradesh: Requested the committee regarding possibilities of undiring than deservol water in the forestore are of oringing man deservol water in the forestore are of oringing man deservol water in the forestore are of oringing man deservol water to have a could be utilised by lift in hadhing Predesh for improve they was round. Integration surpasses all heavy Predesh for implantability in half, where the subject oringing the part of the proper proper to the supplementability of heavy Predesh of the proper proper proper may be exercited to the utilisation of water by lift to it for its man deservation of water by lift to it is middle exercited to the utilisation of water by admitting the selection of water by lift too it is made in the oringing way in the basels are lift, in the deserve of Soil's supple and bigging of left to prover may be intellected to the oringing and bigging of left to the deserve of Soil's supple and bigging of left to the confidence of the proper may be the deserve of soil and bigging or left to the confidence of the confidence of the proper of the preference of the left before the left between the confidence of the utilisation of solver or the left between the confidence of the utilisation of solver or the sufficience of the left between the solver or the sufficience of the left between the solver or the sufficience of the left between the solver or the sufficience of the left between the solver or the sufficience of the left between the solver or the sufficience of the sufficien	BENEFIT SHARING	Binar Conc. stands the designed discharge of Vineturn Courted, Main care at the food of the care is a SROO courted. When care at the food of the care is stands and of the care is stands and of the care of Vineta or Order for United District Courted build be reverted than the transfer of the care at the Courted build be rever the stands for the care of	BENEFIT SHARING	The total utilization on account of Moushhand don may be taken as 5.5 TMC of which 2.25 TMC shall be in Billizand 300 TMC in UK.	BENEFIT SHARING	Domodue Barkar Basin: The Tillaya conservation storage and flood cushon or Tillaya will be utilized by Blant for tillagion. In Gandou and adjacent valley, The Konse conservation storage will be subject by Blant for tillagion in Domodust and adjacent valley on the tillagion in Domodust and adjacent valley and flood cushon of fooms will be utilized by West Bengal, Amswardsh and disflatement hook be tall west Bengal may construct the Sidnehman Hook bed dam for utilizing up to a maximum of 1 bill bilb and it to be basined yield of the friess will be teach for use in Blant upstream of the fire the basined wield of the friess will be talled to the day.
Li North Koel Reservoir Project. Lablane Reservoir Project. Statene Reservoir Project. Statene Reservoir Project. Scheme.			MAJOR HIGHLIGHTS	Saran Main Canal Western Gandak Main Canal & Thermal Power Plants.	MAJOR HIGHLIGHTS	Musekhand Dam	MAJOR HIGHLIGHTS	Domodar Barakar rheir basin. 2. Abyr rieter basin. 3. Maynrakski river basin. 5. Sidhestiwar river basin. 6. Mahamada river basin. 6. Mahamada river basin.
Jharkhand (JH) Bihar (BR)	Uttar Pradesh (UP) Bihar (BR)	Uzar Pradesh (UP) Masiliya Pradesh (MP)	PARTIES	Uttar Pradesh (UP) Bihar (BR)	PARTIES	Uttar Pradesh (UP) Bihar (BR)	PARTIES	Bilhar (BR West Bengal (MB)
MoU regarding Management. Construction, Operation & Mainmanne, and Shaining of Costs and Benefits from and Benefits from (i) the forth food lesservoir Project, (ii) Belane Reservoir Project, and (iii) Batteswareschlan Pump Canad Project.	Minutes of second inter-state meeting on request of their for constitution of a thousand for a subjection of some reter water dispute held by Chairma, CWC on O7.04.2015 at New Debi	Report of Sub Committee and Arrangement regulating Subsidiation of Island Water	AGREEMENT	Minutes of inter-state meeting between officials of Governments of Up and Bihar on Western Gundak canal system of Bihar.	AGREEMENT	Agreement between UP and Bihar regarding construction of Musakhand Dam.	AGREEMENT	Agreement on utilisation of the water resources of the Damodar Bardar, Alloy Mayullach, Alloy Mayullach, Solfscheider, Alloy Mayullach, Solfscheider, Novel Seed, and Maharaki Noon Beer, and Maharaki Noon Beer, and Maharaki Noon Beer, and Maharaki Mayullach and Bardar
5006	2015	A	YEAR	2014	YEAR	1968	YEAR	1978
510	sn	а	GANDHAK	61	KARMANASA	К	ноосгу	보

		Interstate Institutions in Ganga Water Resource Management	Water Resource Manager	nent
Year	Institutions	Genesis	Legal Instruments	Major Functions
1948	Damodar Valley Corporation	The Damodar Flood Enquiry Committee suggested the creation of an authority similar to the Tennessee Valley Authority, USA. A proposal was accepted by the committee for multipurpose development of Damodar Valley.	Damodar Valley Corporation Act, 1948	Power generation for transmission and distribution of electricity. The subsidiaries include flood control, irrigation, soil conservation and afforestation; industrial, economic and other development of the Damodar Valley region.
1955	Chambal Control Board	To ensure efficient, economic and early execution of Chambal Valley Development projects.	The Board was set up by an Agreement between Madhya Pradesh and Rajasthan	Irrigation, power generation, and allied works across MP and RJ, with the joint management of the Central government.
1972	Ganga Flood Control Commission	Established to formulate and implement comprehensive flood management plans for the Ganga Basin through coordinated inter-state measures.	The commission was formed as per clause 5 vide Govt. of India Resolution No. F.C. 47(3)/72 dated 18th April 1972	Provides technical guidance to the basin states for effective implementation of plans.
1976	Bansagar Control Board	On September 16, 1973, UP, MP, and BR agreed to utilise the waters of the river Sone, leading to the 1976 establishment of the Bansagar Control Board by the Ministry of Agriculture and Irrigation to oversee the Bansagar Project in MP.	Resolution dated the 30th January 1976, setting up the Bansagar Board.	Reviews estimates, approves designs & contracts, delegates powers, and ensures cost-effective, timely execution of the project. Monitors progress, allocates funds, enforces guidelines, and oversees resettlement & phased development for optimal results.

		The December 9, 1973, meeting b/w UP and MP led to the establishment of		Efficient execution of the various interstate projects of both States.
1976	Betwa River Board	the creation of the Betwa Board for overseeing the Rajghat Dam and	Betwa River Board Act, 1976.	Betwa River Board Act, Facilitates inter-state coordination, approves 1976. technical designs, monitors project
		Powerhouse project, funded by both states and responsible for reservoir regulation.		implementation, and arbitrates disputes to ensure timely, cost-effective development of the Betwa Basin.
		An Moll was Green bounded the Gree	Docolisticas detad	Governs the equitable distribution of the Yamuna waters among the basin states. It oversees reservoir operations and maintains flow
1994	Upper Yamuna River	basin states of HP, UP, Haryana,	11.03.1995 of the	agreements through rigorous monitoring.
	Board	Kajasthan, and Delhi for sharing the waters of Upper Yamuna.	MoWK, KD & GK set up UYRB.	The board serves as a technical arbiter for water-sharing conflicts. It approves
				infrastructure projects and ensures compliance with river conservation norms.
	National Mission for	Formed under the Namami Gange Programme (NGP) to replace the		Reducing pollution in the Ganga River through various initiatives (construction and upgrading of STPs. etc.)
2016	Clean Ganga (NMCG)	National Ganga River Basin Authority (NGRBA) and oversee the rejuvenation of the Ganga.	Ganga Notification	Rejuvenation and conservation of the Ganga river ecosystem.

ANNEXURE C: Visual Representation of the Drivers of Cooperation in the Ganga Basin



ANNEXURE D: Empowered Task Force: National Mission for Clean Ganga

			R.	Emnowered Task Eoroe (FTE) Meetings	tinas		
				Stak	Stakeholders		
Q	Details	Bihar	Jharkhand	Uttar Pradesh	Uttarakhand	West Bengal	Other Ministries & Authorities
				Meeting Number 2, 03/08/2017			
1171	CAMPA Funds	Not specifically mentioned	Criticised for high crematorium expenditure despite poor community health needs.	NA	Funds confirmed for afforestation along riverbanks.	NA	MoEF&CC: Explained CAMPA fund uses; agreed to release funds for Uttarakhand and coordinate APOs with NMCG.
Funds	General Funds	Mention of overspending (Rs. 1150 Cr. v. Rs. 400 Cr. provision) on ghats and crematoria under NGP.	Overspending concern under NGP.	No fund misuse mentioned; emphasised local enforcement authority.	46 prioritised ghats (Rs. 129 Cr) ready with clearances; requested project execution.	Not specifically mentioned	Funds under sub-heads were exhausted. Approved reappropriation between components; need for approval by the competent authority.
	Water Rejuvenation	Mentioned Ganga Gram villages (4 identified in Bihar); general concerns about project rationalisation.	5 Ganga Gram villages identified; concern over inefficient crematoria investment.	10 Ganga Gram villages identified; authority given to State Ganga Committee for regulatory action.	3 Ganga Gram villages identified, ghats & crematoria clearance obtained for 46 sites.	2 Ganga Gram villages identified	DoDWS: Presentation on 24 Ganga Grams; objectives include waste management, tourism, organic farming, etc.
	Solid Waste Management	SW dump sites identified by NMCG during field visits.	NA	ULBs encouraged to fund basic SWM like dustbins instead of waiting for NMCG.	Dump site identification; poor ULB engagement flagged.	NA	Secretary (Urban Dev): Requested dump site data from NMCG; convergence with NMCG encouraged.
Project Progress	STPs	NA	NA	Show cause & closure notices issued to 1109 polluting industries (up from 764); STPs mentioned as part of long-term solution.	First HAM-based STP awarded in Haridwar; praised as a breakthrough.	NA	DG (NMCG): Push for city-wise comprehensive HAM-based STP maintenance contracts.
	Other Projects	Crematoria projects flagged for rationalization due to overlap and lack of NOCs.	Model stretch; implementation & monitoring quality criticized.	Use of Authority Notification (07.10.2016) to empower SGC.	Request for institutional coordination mechanism between SPMG & CPCB/SPCB NA accepted by MoEF&CC.	NA	Secretary (Tourism): Offered convergence of Tourism schemes with NMCG & Urban Dev. DG (NMCG): Last-mile household sewer connections stressed EP Act Section 5 to be enforced strongly with CPCB/SPCB.
Cor	Comments	NA	NA	Regulatory action can be taken by State Ganga Committees independently, despite constrains (trained manpower, testing laboratories). States were requested to take practical steps as State Ganga Committees have been give power to issue direction.	Requested that an institutional mechanism be setup for coordination between SPMG and CPCB/SPCB.	No representative present	NA
				Meeting Number 3, 26/12/2018			
	CAMPA Funds	FRI's DPR for afforestation plans approved for CAMPA funding; no hesitation from states noted.	Same as others NA CAMPA funds to be used for afforestation per FRI DPR.	Same as others NA CAMPA funds accepted for afforestation; 10% central share to be used.	Same as others NA CAMPA afforestation work supported.	Same as others NA CAMPA afforestation plans to be initiated.	MoEF&CC: Affirmed CAMPA rules are framed and funding for afforestation to come from 10% Central share under R&D.

Utilisation of Funds	General Funds	State supporting financially for Patna sewerage	NA	Largest connection gap (13+ lakh); projects under HAM; Prayagraj & Kanpur major sites; Goitha STP cited as JnNURM-funded with under-scoped house connections	NA	NA	AMRUT: Funding for house connections available. Smart Cities: NITI Aayog proposed a conditional release tied to grassroots action. Namami Gange: 136 STP/I&D projects ongoing.
	Solid Waste Management	NA	NA	Sisamau Nala fully tapped; Prayagraj & Kanpur networks progressing; dashboard suggested for monitoring; Goitha STP delayed due to under-assessed house connections (50K done vs. 2L+ needed)	Not specifically mentioned.	NA	NMCG to become River Basin Authority; One-City-One-Operator strategy for STP operations introduced.
Project Progress	STPs	NA	NA	13+ lakh connections required; One-City-One-Operator model; HAM projects progressing; Goitha STP (120 MLD) delayed due to limited connections; state investment noted	Projects exist but not detailed in this meeting	NA	136 total STP/I&D projects: 106 on main stem, 30 on tributaries; only 40% paid upfront under HAM, balance post-2020.
	Other Projects	State initiatives in Patna for sewerage house connection linkage highlighted.	NA	Meeting proposed at the CM level with the Sec. UD & CEO NITI Aayog suggested fortnightly CMNA Municipal Commissioner reviews.	NA	NA	MoDWS: Called for CM-level oversight and faster UC submissions. NITI Aayog: Pushed for dashboard-based monitoring and grassroots movement. DG (NMCG): Sought institutional strengthening of NMCG as "Authority" and long-term O&M commitment.
				Meeting Number 4, 09/08/2019			
	CAMPA Funds	NA	NA	NA	NA	NA	MoEF&CC accepted the use of CAMPA funds for plantation along the Ganga; AOPs called from the state forest departments.
Utilisation of Funds	General Funds	State not represented; NMCG critical of Bihar's lack of commitment; funds for ODF/SLWM already provided by NMCG.	NA	NA	Mention of funds provided by NMCG for ODF/SLWM in Ganga villages.	State not represented; similar concerns as Bihar.	MoRD: Coordination on waterbody rejuvenation in Ganga districts. HRD: Funds used for educational material; West Bengal completed the assigned task. IOCL: Buyback of treated water; replication discussed. MoAYUSH: Medicinal plantations along Ganga.
	Water Rejuvenation	NA	NA	Waterbody rejuvenation proposed through convergence with MoRD schemes	Waterbody rejuvenation proposed; linked to Ganga Grams and Jal Shakti Abhiyan	NA	MoRD: Working on the rejuvenation of water bodies in the Ganga districts. MoAFW: Organic farming clusters discussed; proposal for a mandatory organic belt along the Ganga.

	Solid Waste Management	NA	NA	NA	Poor condition of MSW in Haridwar noted; concern over readiness for next Kumbh.	NA	NA
Project Progress	STPs	NA	NA	Action reviewed with SMCG, UP; concern over delays & environmental clearance (CETP).	STPs in Haridwar & Rishikesh under KFW scheme; completion by next Kumbh targeted.	NA	NA
	Other Projects	NMCG critical of SGC meeting scheduling; to be raised with CM and CS of Bihar.	NA	CETP environmental clearance (Jajmau); Need for timely completion.	Ganga Gram model villages; completion of I&D, STPs by 2019; long-term sewerage network planned.	NA	MoHRD: Ganga Bal Mela, Ganga Quiz to change mindset. MoEF&CC: DPR for forestry rejuvenation for other rivers. Ayush: Promotion of agroforestry with medicinal plantations. DG (NMCG): Dashboard creation, project tracking, and financial sustainability discussions.
				Meeting Number 5, 10/02/2020			
	CAMPA Funds	NA	NA	NA	NA	NA	MoEF&CC: Will fund nursery and wetland pilots using National CAMPA funds.
Utilisation of Funds	General Funds	VN	NA	VN	NA	NA	NMCG to fund remaining 54,844 ha forestry plantations (CAMPA-unfunded); MoA to scale Paramparagat Krishi Vikas Yojana (PKVY) for organic farming saturation in Ganga Grams; Swadesh Darshan funds used by MoTourism for river-based circuits.
	Water Rejuvenation	Mentioned under PKVY coverage but state-wise progress not detailed.	NA	MoRD & NMCG to jointly revive smaller tributaries.	NA	NA	MoRD: Directed to support rejuvenation of water bodies with geotagging.
	Solid Waste Management	NA	NA	Integration of solid and liquid waste management in river towns mandated, especially in UP.	NA	NA	MoHUA and NIUA tasked to integrate MSW and WWM systems in cities along Ganga.
Project Progress	STPs	NA	NA	Focus on reuse of treated water; all thermal power plants (within 50 km of Ganga) to use tertiary-treated water from STPs.	NA	NA	MoPower: Instructed to ensure zero-liquid discharge and STP effluent reuse in TPPs.
	Other Projects	NA	NA	Ganga Yatra completed: 7.8 crore participants, 1.16 lakh toilets, 302 playgrounds, 118 parks. Proposal for similar events in other states.	NA	NA	MoCulture: Add Ganga to Sanskriti Yatra; set up museum galleries. MoTourism: Create a database of river-based heritage.
				Meeting Number 6, 25/09/2020			
	CAMPA Funds	NA	NA	NA	NA	NA	MoEF&CC: Instructed to fund nurseries and wetland pilots using CAMPA funds.

							NMCG: To find 54 844 ha
Utilisation of Funds	General Funds	NA	NA	NA	NA	NA	plantation (not covered by CAMPA). MoA: To scale up Paramparagat Krishi Vikas Yojana (PKVY) in
							Ganga Grams. MoTourism: To use the Swadesh Darshan Scheme for river-based tourism.
	Water Rejuvenation	NA	NA	Focus on rejuvenating tributaries. (NMCG + MoRD)	NA	NA	MoRD: To map and geotag water bodies for rejuvenation efforts.
	Solid Waste Management	Capacity: 13%	NA	MoHUA directed to integrate solid + liquid waste management in Ganga towns; Capacity: 81%.	Capacity: 53%	NA	NIUA involved in model integration of SWM and wastewater management.
Project Progress	STPs	NA	NA	Emphasis on reuse of treated water from STPs by thermal power plants within 50 km of Ganga.	NA	NA	MoPower: Use treated STP water in thermal power plants - ensuring zero liquid discharge.
	Other Projects	NA	NA	Ganga Yatra conducted across 27 districts: 7.8 cr people reached. 1.16 lakh toilets, 302 playgrounds, 118 parks created.	NA	NA	MoCulture to promote Ganga via Sanskriti Yatra MoTourism to develop heritage circuits & cultural maps Museums & Ganga galleries planned
				Meeting Number 7, 19/03/2021			
	CAMPA Funds	NA	NA	NA	NA	NA	MoEFCC: To fund nurseries and wetland pilots through CAMPA funds.
Utilisation of Funds	General Funds	NA	NA	NA	NA	NA	NMCG to fund 54,844 ha plantation not covered by CAMPA. MoA: To scale PKVY in Ganga Grams. MoTourism to fund river-based tourism via Swadesh Darshan Scheme.
	Water Rejuvenation	NA	NA	Rejuvenation of tributaries planned with MoRD.	NA	NA	MoRD: To geotag & rejuvenate water bodies. MoWR: to develop wetland pilots. CPCB: To identify non-compliant drains.
Project	Solid Waste Management	NA	NA	MoHUA asked to integrate solid + liquid waste in Ganga towns.	NA	NA	NIUA to model integrated SWM systems. MoHUA to implement in 3-tier cities.
Progress	STPs	NA	NA	Treated water from STPs to be reused in thermal power plants.	NA	NA	MoPower: Ensure treated water usage within a 50 km radius of plants.

							MoCulture: Organise Sanskriti
	Other Projects	NA	NA	Canga Yatra across 27 districts in UP	NA	NA	Yatra. MoTourism: Develop heritage
				playgrounds, 118 parks created.			MoCulture: Establish Ganga museums/galleries.
				Meeting Number 8, 22/09/2021			
Fund Utilisation	CAMPA	NA	NA	Used for afforestation, ghat works.	Used for afforestation and ghat development.	Used for mangrove and biodiversity restoration.	Used with MoEFCC for plantation and biodiversity.
	Water Rejuvenation	Wetland rejuvenation initiated in select areas.	Wetland restoration; drain mapping underway.	Riverfront development (Kanpur, Prayagraj), aquifer mapping.	Spring shed protection; drain interception at Haridwar.	Wetland rejuvenation; mangrove ecosystem focus.	MoJS: Drain mapping. MoEFCC: Pollution load reduction.
Project	Solid Waste Management	Solid waste issues in Ganga towns identified.	Action plan for 31 Ganga towns being prepared.	SBM funds used in Ganga Grams and urban ULBs.	Ganga towns covered under SBM; O&M challenges raised.	8 towns under SBM; focus on segregation and capacity.	MoHUA and MoRD convergence encouraged under SBM.
Progress	STPs	Delays in land acquisition; capacity gaps in STPs.	Dhanbad STP delayed due to land issues.	Major STPs in progress; some delays noted.	Haridwar, Rishikesh STPs complete; reviewed for performance.	Garden Reach, Ballygunge STPs delayed due to clearances.	MoHUA tracks AMRUT/STPs; MoD/STPs in cantonments are examined.
	Other Projects	Drainage system improvement in Patna; biodiversity park planned.	Biodiversity parks proposed; wetlands inventory in progress.	Ganga parks, urban greening, ghat beautification.	Eco-sensitive zone development; afforestation.	Eco-tourism and mangrove restoration in Sunderbans.	MoTourism: River cruises, Ganga Yatra. MoEFCC: ESZs, biodiversity.
				Meeting Number 9, 15/03/2022			
Fund Utilisation	САМРА	NA	NA	Continued CAMPA-funded afforestation noted.	CAMPA used for afforestation in ~20,550 ha.	CAMPA & NMCG afforestation with Rs 48 Cr APO.	MoEFCC distributing CAMPA, other schemes.
	Water Rejuvenation	Small rivers & wetland revival plan; scientific plans for 10 wetlands/district.	Same wetlands/focus on small waterbodies via DGCs.	NA	NA	NA	MoEFCC to compile wetland list; NWIC water quality setup.
	Solid Waste Management	New SWM plan for 4500 Ganga villages under development.	Jharkhand cities preparing SWM action plans.	UP cities SWM action plans underway.	Uttarakhand SWM action plans completed and near approval.	SWM plan prep in early stage.	MoHUA: Initiated river-centric urban planning, drain mapping.
Project Progress	STPs	All Ganga cities covered under sewage/septage management.	Monitoring of STP/ghat projects.	Sewage plans in progress; black/greywater addressed.	Uttarakhand far ahead in sewage/septage coverage.	WB Included in sewage/septage roll-out.	MoHUA: Overseeing sewer connections in AMRUT towns.
	Other Projects	10 new tributary DPRs.	Uttarakhand lagging in organic farming; Jharkhand and Bihar too.	Natural farming corridors, ban on exotic fish.	Same organic farming note for Uttarakhand.	Noted organic/afforestation emphasis.	Arth Ganga: DGC strengthening, Arth logo, Ghat haats, cultural tourism, policy on wastewater reuse, Project Dolphin prep (MoEFCC), policy & DGC trainings via NITI Aayog, DST tech support.
				Meeting Number 10, 15/03/2022	2		

Fund Utilisation	CAMPA	NA	NA	Utilised for afforestation and ghat development.	Utilised for afforestation & biodiversity parks.	Mangrove & biodiversity restoration funded via CAMPA.	MoEFCC: CAMPA for riverine afforestation.
	Water Rejuvenation	District level water projects: 11 completed, 5 by Dec 2022, others in pipeline.	Mentioned priority for small rivers, but no state specific data.	Groundwater recharge structures ongoing.	Projects in hill districts under review.	District discussions mention DGC updates, but no specifics.	MoEFCC: Developing wetland inventories. MoJS: Driving dashboard mapping.
Project	Solid Waste Management	Not detailed except referencing ULB engagement.	SLWM in Jharkhand cities underway.	STML/SLWM integrated with SBM and AMRUT.	SBM/AMRUT progress noted; mapping of urban drains active.	ULBs in WB are preparing plans; dashboard uploads are pending.	MoHUA: Reports mapping 7k drains, plans for 47 AMRUT & 49 SBM towns.
	STPs	Bihar reported 11 completed projects, 5 by Dec 2022, others in tender.	Monitoring STP & ghat progress.	PU in Kanpur, Varanasi, Prayagraj advancing.	Uttarakhand STP & ghats underway; villages aiming for ODFNAplus.	West Bengal DGC minutes note STP/ghat tracking.	MoP: engagement on thermal plant reuse; MoHUA tracks AMRUT sewer connections
	Other Projects	Drainage improvements and biodiversity covered under LID.	STP/Others under monitoring; organic farming noted.	STP/ghats monitored; ODFNAplus plans underway.	Ghats in Badrinath prioritised; ODFNAplus commitment.	DGC uploads and asset tracking being strengthened.	MoEFCC: Pushing Dolphin action plan.
				Meeting Number 11, 20/04/2023	3		
Fund	Fund Utilisation	NA	NA	NA	NA	NA	MoEFCC: Driving Dolphin sanctuary and wetland policies. Finance/Accounts: TSA transition completed; ₹2,220 Cr allocated for FY 22-23 has been fully disbursed. ₹4,000 Cr budgeted for FY 23-24. Clean Ganga Fund (CGF) corpus: ₹733 Cr.
	Water Rejuvenation	NA	NA	NA	NA	NA	National Ganga Council 2nd meeting (Dec 2022). PRAYAG monitoring centre launched.
Project	Solid Waste Management	NA	NA	VN	NA	Tunnel debris dumping flagged; Geo tagging drains & arrestor screens to be installed (2,400 drains).	MoHUA/U20/DHARA initiatives under RCA; drain mapping under AMRUT.
Progress	STPs	NA	NA	NA	NA	NA	PM inaugurated 20 STPs + 7 sewer networks in Kolkata; 55 MLD STP in Varanasi.
	Other Projects	NA	NA	MV Ganga Vilas river cruise flagged off; 11 jetties in Varanasi, 22 planned in Bihar; Ganga Sanskriti Yatra & museum space.	Focus on pressuring debris control on Uttarkashi riverbanks.	Hilsa fish ranching upstream Farakka: 90,433 adults ranched; 8 lakh seeds released; cage approach trial underway.	Arth Ganga verticals: Natural farming, sludge/wastewater reuse, JALAJ livelihoods, Ganga Praharis, RCA expansion, digital capacity building and certification programs.
				Meeting Number 12, 10/09/2024	4		
	Utilisation Certificates	Pending UCs for IHHL to be submitted by Oct 2024.	Pending UCs by mid-Sept 2024.	Pending UCs by mid-Sept 2024.	Pending UCs by mid-Sept 2024.	Pending UCs by 1st week Oct 2024.	NA

•							
Fund Utilisation	САМРА	NA	NA	NA	NA	NA	MoEF&CC to submit report on Chambal Dolphin Sanctuary (interstate with UP, MP, Rajasthan).
	> Non-CAMPA Funds	Jamalpur I&D/STP funded under AMRUT; DPRs for Arah, Barauni, Buxar STPs pending.	NA	Sewerage work (some) funded under other schemes; drone survey ongoing.	NA	Request for DPR prep funding clarified to be covered under 4% centage.	NA
	Water Rejuvenation	Mapping of nallas in 10 Ganga districts by 31 Oct.	Mapping of nallas in 1 Ganga district by 31 Oct.	Mapping of nallas in 27 Ganga districts by 31 Oct.	Mapping in 7 districts + tributary focus (Bhela, Dhela, etc.).	Mapping in 12 districts by 31 Oct.	PRAYAG: 250 STPs >1 MLD; 90 to be OCEMSNAlinked (Bihar: 8, WB: 40, UP: 11, UK: 18, JH: 13).
Project	Solid Waste Management	Tagging of villages with FSTPs (Faecal Sludge Treatment Plants).	Tagging of villages with FSTPs (Faecal Sludge Treatment Plants).	Tagging of villages with FSTPs (Faecal Sludge Treatment Plants).	Tagging of villages with FSTPs (Faecal Sludge Treatment Plants).	Tagging of villages with FSTPs (Faecal Sludge Treatment Plants).	All States to align reuse policies with national framework; promote treated wastewater reuse.
Progress	STPs	STP DPRs pending: Arah, Barauni, Buxar. STP works delinked from sewer network in Motihari/Daudnagar.	No new STPs; future projects on tributaries deferred.	DPRs submitted: Manikpur, DDU Nagar. Others (Kanpur, Agra, Prayagraj) due by 30 Sep. Power to STPs by Sep 15. Land	Gauri Kund site shift; STPs on tributaries to be expedited; Udham Singh Nagar project due by 31 Dec.	DPRs due: Srirampur, Siliguri, Shantipur by Sep 30; others by Dec 31. Land issue at North Barrackpore in	Ministry of Power to enforce use of treated water in TPPs. No new exemptions. 61 TPPs to comply.
	Other Projects	ODF Plus: 7 villages to be declared; 431 verifications due by Dec.	ODF Plus: All verifications due by Dec 15.	ODF Plus: Declare 1 village urgently; 1581 verifications pending.	ODF Plus: 184 verifications due by Oct.	ages to 1s by Feb	CETP: Gorakhpur DPR + Unnao agreement (UP) due in 1 month; Ministry of Tourism to train guides, develop GangaNA based tourism; Natural Euraring model farms by
				Meeting Number 13, 09/12/2024	4		
Fund	Fund Utilisation	GrantNAinNAaid via DoDWS (FY15NA19) NA ₹32.63 Cr UCs pending (under rural sanitation/ODF interventions).	₹0.95 Cr UCs pending (via DoDWS).	₹38.18 Cr UCs pending (via DoDWS).	NA	₹36.83 Cr UCs pending (via DoDWS)/	DoDWS: Follow up on pending UCs with States at the Chief Secretary level; Annual Accounts of NMCG for FY 23-24 adopted. Audit certified statements as fair. Audit observations to be addressed in 2024-25.
	Water Rejuvenation	District Ganga Plans (DGPs) to be prepared for Bhagalpur & Nalanda (via GIZ). Others via academic institutions.	NA	DGPs for 29 districts prepared/underway with support from GIZ & IIPA. Districts: Shahjahanpur, Moradabad, Bareilly, etc.	DGPs for 12 districts are being hand-held by GIZ. Example: Udhamsingh Nagar, Haridwar.	Nadia & Hooghly to be supported by GIZ.	Natural Farming: MoA&FW to lead; NMCG to support. ₹2431 Cr scheme approved. 42 workshops held; 2 model farms (Sambhal, Haridwar) funded for impact study (results by 30.06.2025).

Srirampur: DPR comments due 15.01.2025. Siliguri: Land to be located by 15.01.2025. Shantipur: Alternative land is being located. 12 towns (incl. English Bazar, Howrah, etc.): No land; planning FSTPs instead; action plan due 15.01.2024. Cantonment Board clearance due by 31.12.2024.	Ganga Knowledge Portal (gyanganga.ai) launched. Annual Accounts for FY 23-24 Annual Accounts for FY 23-24 Annual Accounts for FY 23-24 adopted; ODF+; verification to complete by Feb 2025. DGPs for Nadia & Hooghly via GIZ. ED(F): Emphasised UCs follow-up; DoDWS: To pursue at the CS level.		STP at Khardah being built DDWS: ₹75 Cr spent, UCs to be with state funds.	GIS mapping of wetlands NGRI (aquifer mapping), River underway. Cities Alliance (URMPs).	T advisory, Gobar Gas → Min. of Tourism: Issued SWM advisory to states; training in 24 cities.	(Siliguri, Shantipur, Haldia, Diamond Harbour, etc.) Kharda STP with state funds Land issues in several towns (e.g. Rishra, Howrah).
	* *		STP at Khardah being with state funds		MoT advisory, Gobar Gas FSTP in Champadani.	Multiple DPRs under proce (Siliguri, Shantipur, Haldi Diamond Harbour, etc.) Kharda STP with state fun Land issues in several tow (e.g. Rishra, Howrah).
Gauri Kund STP: Design modified and approved by IIT Roorkee; completion by 30.04.2025. Kalyani River: ROW issue resolution by 15.01.2025.	ODF+ survey to be completed by 31.12.2024. Natural Farming: Model farm in Haridwar. DGPs for 12 districts are being hand-held by GIZ.	ທ	NA	Mention of the Kalyani River encroachment resolution.	NA	Gauri Kund STP: by 30.04.2025 US Nagar STPs: staged completion till April 2025 Kalyani River: encroachments cleared.
Agra: DPR comments from TPA shared; response expected in 15 days. Kanpur: Drone survey complete; DPR due 31.12.2024. Prayagraj: Drone in progress; DPR due 31.01.2025. Varuna Action Plan unsatisfactory; action demanded within 15 days. Gulaothi STP: Land to be procured by 31.01.2025. Dadri STP is directed to use treated water. CETP: Gorakhpur tender refloated; Unnao contract not signed.	ODF+ verification of 1000 villages is ongoing till 31.12.2024; 67 villages to be declared ODF+. DGPs underway in 29 districts; URMPS for Kanpur & Ayodhya completed; State to notify implementation committee by 31.12.2024.	Meeting Number 14, 11/03/2025	Mention of UC utilization (DDWS) and land procurement.	Aquifer mapping, URMPs for Kanpur & Ayodhya.	Mention of segregation advisory via MoT; drone survey for new drains in Prayagraj.	Gulaothi STP: land by 31.3.2025. Varuna River projects approved. Dinapur: 27 new drains to be tapped. Kanpur & Prayagraj DPRs progressing CETPs in Gorakhpur & Unnao.
NA	ODF+ Village verification completed by 15.12.2024.		FN	VN	NA	FN
Barauni DPR cost being revised (was ₹531 Cr for 25 MLD). Revised DPR due 31.12.2024. Hajipur: Power connection by 31.12.2024. Mokama: Railway NOC due by 31.12.2024. Kahalgaon: Access road issue to be resolved by 31.12.2024. Dehri on Sone: Land issue by 31.12.2024. Jamui, Motihari, Daudnagar: LoA process to be expedited by 31.12.2024.	ODF+ Village verification ongoing; 7 villages to be declared ODF+, DGPs: Bhagalpur & Nalanda (via GIZ).		NA	Aquifer mapping in Prayagraj-Kanpur stretch (via NGRI).	NA	Hajipur: power connection by 31.3.2025. Jamui & Daudnagar: work ongoing. Motihari: contract pending. Kahalgaon: road issue to be resolved. Dehri on Sone: land transfer in progress Mokama: railway NOC received.
STPs	Other Projects		Fund Utilisation	Water Rejuvenation	Solid Waste Management	STPs
Project Progress			Fund U			Project Progress

				CETPs at Gorakhpur (4MLD) & Unnao (2.5MLD); Drain	Kalyani River encroachment	DPR town reclassification	DoWR: pushing for eNAflow compliance in Yamuna. MoP: Coordination on treated water
	Other Projects	GIS layer of wetlands ready.	NA	survey via LIDAR River Cities Alliance NA URMPs.	Sanitation status survey (ODF/ODF+) underway.	existing plants (e.g. Gobar gas to FSTP).	MoT: Ecotourism promotion, dolphin sites. DDWS: Sanitation survey; 393 drains inventoried.
				Meeting Number 15, 24/06/2025	2		
Fund 1	Fund Utilisation	No funds specified; mostly NMCG funded DPRs and STPs.	No specific mention; multiple STPs under different statuses.	Funds sanctioned for Gulaothi STP land by 15 July.	No mention of fund type, but multiple DPRs/STPs discussed.	DPRs in progress and submitted; no fund types mentioned.	DoDWS: ₹953 Cr disbursed to Ganga states (FY 2015NA19); UCs still pending.
	Water Rejuvenation	Wildlife clearance delays for Kahalgaon & Bhagalpur HAM projects.	Several STPs in Dhanbad & Petia. Delays due to forest land/local agitation.	Drone surveys in Prayagraj completed. Agra drains DPR approved. Varuna & Dinapur DPRs in progress. Aquifer mapping with NGRI; DPR by 15 July.	DPRs prepared for Udhamsingh Nagar, Gauri Kund STP 70% done; encroachment on Kalyani river sewer line cleared.	English Bazar, Haldia FSTP, Shantipur, North Barrackpore, Diamond Harbour, Howrah, etc. at different DPR stages.	NGRI: Aquifer mapping with UP Ground Water Dept.
	Solid Waste Management	NA	NA	NA	NA	No new info; FSTP DPRs in process (e.g., Haldia).	DoDWS: ₹953 Cr for SWM & ODF in Ganga Grams; UCs pending.
Project Progress	STPs	Mokama STP operational. Power pending at Hajipur. Kahalgaon road issue resolved. DehriNAonNASone land NOC received. Motihari, Jamui, Daudnagar NA LoA signed. New site for Panderkali STP; Gobindpur STP under realignment. Joriya STP forest share reduced.	Petia STP local agitation (1.5 months for resolution). Sizuwa STP resolved; work to resume.	Agra DPR approved. Kanpur DPR approved. Gulaothi STP: land fund sanctioned. Numayadahi & Kodra STPs planned. Prayagraj: drains to be connected to existing STPs.	Gauri Kund STP: 70% done; to begin trial by 30 June Kalyani River: 1500 encroachments to be cleared Kotdwar STP: Army to provide alternate land.	Multiple DPRs under preparation or review: Siliguri, Serampore, Shantipur, Khardah, Howrah, Rishra, Champadani, etc.	NMCG is encouraging the reuse of treated water (national reuse policy alignment requested from states).
	Other Projects	Income Tax exemption granted to NMCG under Section 10(46A).	NA	CETP at Unnao (2.5 MLD): enforcement actions by UPPCB/CPCB; state to convene meeting.	Kotdwar STP site to shift (Army land); NMCG site visit planned.	Uluberia: Consultant terminated, new tender floated Various DPRs in the pipeline.	NMCG is adopting Insurance Surety Bonds for bid/ performance/ mobilisation security. GST guidance for HAM projects released. Comparative analysis of project time under NMCG vs AMRUT requested by the Secretary.

ANNEXURE E: All India State Water Minister's Conference

			2nd ALL IND	2nd ALL INDIA STATE WATER MINISTERS' CONFERENCE 2025	
S. NO.	STATES	REPRESENTATIVE	DESIGNATION	STATES POINT OF VIEW	REMARKS
	Andaman and Nicobar Islands	Chandra Bhushan Kumar	Chief Secretary	836 islands, 31 inhabited, 3400 mm rainfall in 117-209 rainy days, indigenous rainwater harvesting by tribes, example of Chaura island- had their own dugwell and water conservation method. Modern day desaination plant set up and trying to improve quality of structures. Urban area, 33 MLD 1.8 lakh people, 24,4 MLD demand, Water from other islands to be brought is suggested. Rutland Water Supply project- spreading pipelines. Dhani Khadi Dam 6.6 MLD water will be increased for mitigating summer water problem. Water givenance problems. Normative-Uncertaininty, Fragmented, Organized irresponsibility. Demand side management governance, seasonality, and resilience are the issues. Norm dictated governance—133 If person that needs to be managed (100 I/person in Europe) Water reuse not practiced much due to organized irresponsibility, grey water management issues. 226 amrit sarovar, 20 drains, 100s RWH, 2700 wetlands are tried to be interlinked. Future water governance—multiple sources, jul sanchay, certainity, audit, inter connectedness, community awareness, hydro-social concepts.	NA
74	Andhra Pradesh	Nimmala Rama Naidu	Minister of Water Resources	The rice bowl of India, 62% population depends on agriculture. 966 mm rainfall average. 5 major rivers, 35 medium and minor rivers. 108 reservoirs Issues- Bifurcation in 2014 affected resources and economy, no capital city, no major industries, recurring droughls, lower riparian state, limited storage, frequent floods and eyclones. Only 50% area is cultivable, 39 TMC water conservation structures. Vision: make the state droughtproof, reduce IPC-IPU gap, increase water use efficiency, tap surplus flood flows, modernization, etc. Dr KL Ros- Interlinking of rivers. Polavaram frigation in Godavari projectmultipurpose terminal reservoir-960 MW power, 1,128.4 m spillway. 86 ongoing projects. 28.78 TMC for industrial purposes. Veligonda project- for fluoride-affected and drought-prone areas of Praksiam district, etc. HNSS project- Water to Ananhapur and 5 drought-prone districts of Rayalascema. 85 projects are ongoing. Groundwater and micro-irrigation. 1st to have geotagged borewells. 710,000 acres of irrigable area stabilised. Adopting technology- APWRIMS. Storage improved by 53%. By the end of the Khariff season 135% of reservoir capacity was utilised.	State Reorganisation and Resource Constraints: IPC-IPU Gap. Interlinking of rivers and the large dam, Polavaram. Improvement of the storage facilities
rs	Arunachal Pradesh	Mama Natung	Minister Home & Inter State Border Affairs, Public Health Engineering (PHE)	Himalayan range - perrenial source. 300 m conservation act in Arunachal Local water sources are exploited. Igam project to recharge water bodies. Trenches in mountain to conserve water causing rehabilitation in dry villages 772 annit sarovar. 1st state to achieve JIM mission in Feb 2024. Household done, schools left. No issues of funding.	Transfer of blame to the centre completely. Efficient in implementing of the JJM.

Success and Innovation in Jal Jeevan Mission. Floods and Erosion and the Central Objective of the Kosi High Dam. Asset Management is a need of the hour, especially for embankments.	NA	Discussed about JJM.	NA	Inter-State Water and external water supply is a vexing challenge to meet Delhi's water needs. Asset Management and reducing non-revenue water in the urban context. The conversation mostly focused on DW supply.
Bihar government launched a tap water supply mission in 2016, when only 2% of households had access to tap water. Working in mission mode, Bihar provided tap water to all rural households, achieving in 2019 what was later adopted as a national campaign. The Public Health Engineering Department and the Panchayati Raj Department constructed 12,936 water supply schemes, providing 1.74 crore household comections. Special efforts were made to ensure safe drinking water in arsenic, fluoride, and iron-affected areas, benefiting 30,207 rural waters. About 50% of these schemes employ women as pump operators, promoting women empowerment. Panchayat-level repair teams ensure real-time issue resolution, reducing service interruptions. "Office Day Zero" mandates officers to inspect projects at the grassroots level instead of sitting in offices, ensuring proper implementation. The initiative has transformed Bihar's economic, social, and cultural landscape, enhancing social harmony and significantly improving public health by reducing waterborne diseases like diarrhea and hepatitis, leading to a decline in child mortality rates. Additionally, the project has created over 2 lakh direct employment opportunities for rural youth and women. The Bihar government's MBS water supply scheme, already implemented in 12 locations, benefits around 20 Panchayats per installation. The state aims to provide 135 liters of water per person per day, ensuring sustainable water conservation in alignment with Mission 207, a vision for long-term water security. The Bihar government's MBS water supply project operates in 12 locations, benefiting 20 before 2047 to shift from goundwater to surface water supply using modern technology and smart meters. Bihar's water levels vary: North Bihar: Water at 10 feet. Central Bihar: Water at 100+ feet. South Bihar: Water at 2,300+ feet. To tackle scarcity, Ganga water is transported 200 km to South Bihar, but had and destruction. Embankments exist but weaken yearly, leading to crop and property loss. A long-term	major efforts since 2019. 47000 water resources marked. 24000 old water sources were renewed and new sources were established. 64000 resources for transfer of high to low water region. More than 12000 check dams have been made. Rainwater harvesting and water conservation structured are being constructed. 37000 wells and 2,03,000 hand pumps have been installed. 25000 acres land is being irrigated. 17,80,00,000 plants have been planted. Awareness events are also planned. Religious stature of rivers is also considered and treated accordingly. Awarded with numerous prestigious prizes for conservation efforts. Jeevika didi.	62,844 cubic m water-48,296 cubic m surface water - 14,548 cubic m ground water. Rivers like Mahanadi, Shivnath, Arpa but in reality there is ground water level problem, due to political reasons there was a 2 year delay in the Jal Jeevan mission despite which it is actively progressing, 50,03,552 families was the target kept. 40,21,116 i.e. 80% target has been achieved. 4,313- Har ghar jal ghoshit villages, 2,857 har ghar jal pramant villages. 1,04,935 women water checking volunteers have been trained and equipped. State level water quality commission set up. 27 districts have been equipped with research labs. Toll free number generated.	More than 2 lakh water conservation structures. learn from tribes. Reduce water wastage. Mindful consumption.	integrated water management, population of around 30 million, migration of around 200,000 people to Delhi. present water demand is around 1250 MGD while it is getting 990 MGD. does not have its own source.388 MGD from Yamuna around 255 MGD while it is getting 990 MGD. does not have its own because the supply belin has around 4800 tubewells from widh we get 126 mgd of Water. increasing Demand Due To unplanned urban growth but the water supply is not matching with the demand mainly Because the supply from external sources has remained constant. 40 to 52 non-revenue water. private partner who can not only bring in the fund part but also the Technology Delhi's 52% water is non-revenue water is mainly because of the ageing Infrastructure and mismanagement. The Model of O&M 123 Primary UGR 480 Secondary UGR and around 15000 plus kms of Distribution Network it Requires Lot of any repair or replacement and Augmentation Requires Lots of fund. Malaviya Nagar Water Services. Malaviya Nagar project was funded in The ratio of 70:30 70 was invested by Delhi Government for Capes Works and 30 But was invested by the O&m Partner. Plan for Improvement Station and Replacement of old and leaking damaged networks are also the formation of District Meter Area- o&M helps in the same. Dashboard for customer complaint Management. house service Connection increase from 35000 to 58000 and The NRW reduce from 70% to 34%. Project Funded Under JICA. cover all the houses to the sewer line 100% sewer coverage of all the Areas, treatment of sewage aggregates. 600 mgd unused.
Minister of Public Health Engineering Principal Secretary	Minister for Rural Development	Deputy Chief Minister	Minister of Water Resources	CEO Delhi Jal Board
Niraj Kumar Singh Santosh Kumar Mall	Shravan Kumar	Arun Sao	Kedar Nath Kashyap	Shilpa Shinde
Bihar		Chhattisgarh		Delhi
4		w		9

NA	NA	Narmada Project illustration.	Governance challenges highlighted Non-riparian status and external dependency from inter-state project such as Bhakra	AMRUT and JJM Asset Management and improving efficienc y Required funding for JJM
5 elements- water, state, civil society, private buisiness, farmers. Rajnandgaon template- many naxal affected areas, primarily agrarian, mostly depends on paddy. Significant water stress. Paddy needs ground water extraction. More than 42000 borewells used. Attempts to convince farmers for crop diversification- 10 point programme for both demand and supply side of problems. Multi village scheme, Lineament fracture zone, water scarcity villages, drainage network villages. Community involvements, plantations and building structures. Post implementation- more than 51000 structures, 32% crop diversification etc. Ground water levels rose by nearly 2.04 mbgl. 12 departments worked together. Chhattisgrah ranks 1st in India across most categories in SJB. Reform. Perform. Transform. ABIS created demand for maize with renumerative prices above MSP. Behaviour change.	Challenges- Unequal distribution of water resources. GJ has 6% of total geographical area of India but 12.36 % of water stressed area of India. 58.6% of total area of Gujarat is subject to water stress due to arid, semi-arid, and saline conditions. 20 major, 90 medium and 1,006 minor irrigation schemes. 1.87 lakh check dams, 3.23 lacs farm ponds, 0.37 lacs ponds deepened. Local level issues- stress on resources, difficulty in land acquisition. governance practices adopted. More than 1 lakh projects completed. 200 lakh man days employment generated. Jal Shakti Abhiyan also in progress and yielding positive results. Case study of Navsari district. Amrit sarovars made. River rejuvenation with help of NGO launched. check dams made, capacity increased.	gujarat faces semi-water scarcity. Sardar Sarovar dam was completed under Narendra Modi's term. Narmada's water is used in the dry areas of Gujarat like Kutch, Saurashtra. Water conservation and management processes are in progress. Various check dam, tubewells, ponds etc have been made for water conservation. Old rivers have been revived and improved. Sujalam sufalam yojana has been fruitful in raising water levels and imporvement in the agricultural output and the lives of farmers as well. People are using rainwater harvesting, micro irrigation and water conservation methods. The cleanliness of water resources is also being maintained. Check dam, pond mud has increased productivity, given employment and increased water levels. Since sep 24, Jal Sanchay Jan Bhagidari initiative has been launched with more than 24,000 beneficiaries. Atal Bhujal Yojana aims at increasing ground water level.	Water secure Haryana. Youth, poor, women, famers are pillars of the futuristic mission. As non-riparian state, Haryana has holistic approach with 544 canals with Bhakra dam system for north western and western parts, Western Yumana for its north-eastern and central parts. Water is a scarce resource especially in southern parts of Haryana. Lift canal systems in the southern parts is implemented to meet the challenge. Fragmented governance was a major challenge. Systematic approach of governance was taken up. Haryana water resource conservation and management authority, Haryana pond and waste water management authority, and Haryana Saraswati board and were established. Haryana has formulated reuse of waste water policy which aims at 100% euse of waste water by 2028. Model state integrated water managemnt system will help amen Haryana water resources act 2020. Integrated water resources plan was formulated on basis block level data of demand and supply in 2023.	Committed to ensuring "Har Ghar Nal, Har Ghar Jal." Issued a notification for the reuse of treated wastewater, with rapid execution. Groundwater depletion is a concern, but Haryana has 177 sewage treatment plants (STPs) with a total capacity of 2137 MLD. Currently, 1487 MLD treated water is being generated, aiming for 10004 MLD by Dec 2025 and 100% reuse by Dec 2028.Under AMRUT 2.0, 44 cities are covered to improve water supply and reduce non-revenue water (NRW) by installing district metering zones and bulk flow meters. Energy-efficient pumps and equipment with a five-star rating are being installed in 34 approved cities, reducing costs and greenhouse gas emissions. 216 villages in Haryana now receive drinking water through Ranney wells in the Yamuna floodplains. Efforts are ongoing to include water-deficient areas like Mewat in canal-based water supply schemes. Plans to shift water-scarce regions to upstream canal locations, requiring significant investment. Haryana is seeking a special financial package detection, and repairs. Currently active in 13 cities, with 29 more approved under AMRUT Mitra. Haryana urges the central government for additional financial aid under the Jal Jeevan Mission extension to strengthen water security efforts.
Secretary Department of Water Resources	Minister of Forest, Environment, Climate Change	Minister of Water Resources and Water Supply	Minister of Irrigation & Water Resources	General Minister for Public Health Engineering
Rajesh Kumar Topu	Mukeshbhai Patel	Kunwarjibhai Bavaliya	Shruti Choudhry	Ranbir Singh Gangwa
	Gujarat			Harayana
	٢			ос

		Keshni Anand Arora	Chairman Haryana Water Resources Authority	Key issues- Depleting water table, water logging, Salinity. Worked on data collection according to CCWB and found 88 over-exploited blocks. Tried to analyze gap analysis at village level. Water scenario was analyzed. Total water availability- 20,93,600 crore 1. Total demand- 34.96 BCM Gap- 14.02 BCM which is procured from ground water pressuring aquifers. Agriculture and horticulture require most water. integrated water resource sharing is required. Data shared with Panchayat. 1948 villages were in red category. Datas and maps were analyzed shortly. Action plan worked on formation of TWRAP, required interventions. actionable plan, reducing demand supply gap, and data- based decidion making. Portaal was also made. Mera Paani meri vorasat. Monetary renumeration for people reducing water pressure by diversifying their crops, and water conservation methods. IWRAP aims to bridge water deficit og 6.9 BCM. 75% of targets achieved. Major achievements- crop diversification, direct seeding of rice, varietal interventions, micro irrigations, etc. Working on restoration of water bodies and storages. 27 projects of irrigation based in using treated water. Working for reclamation of water logged areas by vertical and horizontal drainage and prawn cultivation. Perceptive increase of 11% in groundwater recharge. Coordinating with world bank for funding Working on jal shatit kendra, recharging wells, river interlinkings, recharging schemes. Now working on automation and monitoring in water management using SCADA and RTDAS. SWRMS for surface water management. Community participation is emphasized. Eco clubs are trained. New water sources are being created.	GW depletion and cropping pattern necessity and focus on agriculture working on automation and monitoring in water management using SCADA and RTDAS Tech deployment
6	Himachal Pradesh	Mukesh Agnihotri	Deputy Chief Minister	Devbhoomi. Jall jeevan mission completed. Provided tap to 17 lakh households, climate change, low and unregulated rainfall/snowfall leading to drying of water sources difficulty in providing water. Melting of glacier 20-30 m every year. Due to changes in air-water patterns Pressure on surface water resources increasing water security. Issues. Measures like ground water recharge, rainwater harvesting, etc. for sustainable water security. Pipelines freeze in tribal areas like Spiti, Kannaut, etc. specifically. Tough geographical conditions in hilly areas. Therefore, need specific funding for heated pipelines, anti-freeze systems, insulated taps, ect. Fulfillment of center's commitments. HP has made a 1300 cr plan for water and snow conservation by cleaning ponds, re-establishment, snow pits, etc. Rainwater harvesting systems establishment needed. Cloud burst has caused heavy damage of about Rs. 2000 cr in past 2 years. Funding for agriculture irrigation systems. 4000 cr is insufficnct for water pipelines and drainage project. Due to high forest cover, building infrastructure is more cost intensive. Specific outlook for hilly states.	Progress in JJM. Environmental Risks such as glacier melting, cloud bursts. Infrastructure suitable for the hillside in the water delivery system. Infrastructure finance is suitable for the hillside.
10	Jammu and Kashmir	Javed Ahmed Rana	Minister for Jal Shakti	J&K faces significant water management challenges due to rapid urbanisation, unsustainable agricultural practices, excessive groundwater exploitation, and climate change. A national convention highlighted the urgent need for public awareness and systematic water conservation efforts. J&K has 20 districts, with major water sources including the Wular Lake (the largest freshwater lake in India). Dal Lake, and wetlands like Hokersar and Gharana. However, climate change and ecological imbalances threaten these critical water bodies. Infrastructure projects in J&K have suffered delays, especially in border regions like Pir Panjal, due to frequent ceasefire violations. Many areas were left out of the Jal Jeevan Mission due to instability, and a request has been made for special provisions to include these uncovered areas. The 2014 Kashmir floods caused severe damage, underlining the need for a comprehensive master plan for flood control and erosion management in both Jammu and Kashmir. Restoration of major lakes and wetlands is essential to preserving water availability. J&K has also proposed hosting a water conservation workshop, though the upcoming event was allocated to Odisha. The region is working to revive stalled projects that suffered due to political instability and conflict over the past five years. A special focus is on improving wetland conservation and restoring neglected water bodies. The government has emphasised the importance of ecological balance and sustainable water management for the future of the region. The session concluded with a poetic reminder of the need to protect and preserve natural resources for future generations.	Border area challenges manifest in lower JJM penetration in certain areas. Domestic conflict infrastructural gap.

Karnataka	D. K. Shivakumar	Deputy Chief Minister	Internate change, water politution, competition for water, 100d security, and the number of water users are also increasing. Development of, and water needs improvement. India supports 80% of the world's population with just 4% water resources. India also needs improvement. India supports 80% of the world's population with just 4% water resources. India also needs to cope with greater industrialisation. Storage capacity is 253 billion cubic m. Reforms- To curb illegal withdrawal of water Karnataka Irrigation Act 1965 was amended in 2024, to avoid illegal tapping of water so that it reaches the right individuals. Officers conducted an apt enquiry to ensure proper implementation of the act. Provision of a task force to the police. Farmers are not allowed to suck water from canals. A new state water policy was enacted in 2022. New legislation and acts covering water resources need to be addressed for changes's amendments. 29 legislations need to be covered. 14 at the centre level and 15 at the state level. New administrative governance bodies with a mandate, power, authority, reorganisation aligning to capacities and requirements, new standard operating procedures, tactical amanagement processes, and tools and practices, water infrastructure development. Pending Issue-CWC clearance to the Mekedatu project and the balancing reservoir infrastructure of the Cauveri river, dispute resolution for helping Tamil Nadu. 400 MW of power will be generated from it. A 5,300 cr grant was announced by the government for Upper Bhadra projects for providing irrigation, but no money has been released. Modification of the order of 2011 on the Gazette notification Krishna Water Tribunal. Direct NBW on the Maladayi Water Dispute Tribunal and kalasa banduri nala. NWD agency to revisit state-wise proposed for Kamaraka. Bengaluru droughts of drinking water. Upper Bhadra projects for the central Karnataka Bengaluru droughts of drinking water. Upper Bhadra projects for the central Karnataka drought-prone areas. funding. Krishna water dispu	TN issue seemed fleeting.
	Gaurav Gupta	Additional Chief Secretary	31 districts, 240 taluks, 6.11 crore population 1608 cubic m/ person/ year water availability 191700 sq km drainage area with 7 river systems 3438 annual yield mostly from east flowing rivers which cannot be tapped thus major dependence on Krishna and Cauvery. Irrigation potential of 20.40 lakh Ha (75%) achieved so far. 4 SPY (KBNIL, KNNL, CNNL, VML) 805.95 TMC storage capacity, 52% from major and medium irrigation projects.365 TMC usable gound water with several over-exploited regions for which Upper Bhadra and Yettinahole projects have been put in place for recharge. Modernizing more than 100 years old Krishna Sagar Dam. EAP approved by CWP 136 sluice gates replaced. Tungabhadra dam restoration-important for Tamil Nadu, Karnataka, Andhra Pradesh. Proposed to restore the loss of capacity of 26.618 TMC. Mekedatu balancing reservoir-planned to have storage capacity of 67.16 TMC. Utilize 4.75 TMC consumptive and generate 400 MW power. Dam rehabilitation project- 22 dams- 452.92 TMC. 4 awards received. Almatti Dam- create additional 100 TMC capacity. Upper Bhadra project- Micro irrigation, water recharge, augmentation. Augmentation of Van Vilas Sagar- modernization of 104 km canal. Yettinahole project- Water from western rivers is diverted to drier regions. Funded by state alone. Karnataka Irrigation Act 2024- prevent misuse of water, digital monitoring, ABHY for groundwater. KC and HN valley	NA
	Jeevan Babu. K.	MD of Kerala Water Authority	common person, engineer and government's perspective. Challenges- increasing scarcity, unequal access, environmental degradation, conflicts, large number of stakeholders, climate risk, disasters risk, 35% coastal erosion, pollution, groundwater depletion. Kerala- 859people per sq. km. 26% pop. in coastal belts, 44 rivers. small drainage basins, 590 km coastline. Rainfall-3000mm. Rapid runoff due to steep terrain. urbanization is heavy with change in lang use and gap in data collection. Cloud bursts cause flooding but drangelises, dtrengtheing governance. RBCMA is in final stage of approval and IRBM is being formed. Kerala WRIS for data collection in 2021 and used for forecasting, early warniing systems, sustainable watta conservation in 2021 and used for forecasting. Haritha Kerala Mission for community driven watter conservation. 914 gram panchayat and 105 block panchayat focuses on water conservation, watse management, organic farming, Jalasamrudhi Kattakkada model in Thiruvananthapuram to restor water bodies and groundwater recharge sustainably. Navakeralalm Mapathon using technonlogy for physical survey, 230 gram panchayats mapped. Reclamation activities in 44 gram panchayats across 6 districts. Ini Njan Ozhukatte- to revialize waterocurses through mass mobilization and participatory campains. Involves local self- gout. institutions, MGNREGS, KSITM and RKI to reclaim wester ghat waterocurses to avert disasters. 234 labs sanctioned. 150 operational in higher secondary schools. Neeruravu scheme- joint venture of Haritha Keralam and MGNREGS focus on soil and water conservation in specific areas. Water budgeting-harvesting in Thrissur Current focus- JIM, RKI, KIIFB, site-specific practice, strongthening canal networks, rejeuvenating rivers and streams, pollution control, desilting tributaries, etc. Support reuired- budget for IWRM and RRCMA, integrated approach, technical expertise, support in human resource, financial model based on topography, interstate coordination.	NA
	Retd. Brigadier Dr B D Mishra	Governor	High altitude area it is at 11562 feet the altitude, 59146 sq km.	More philosophical than regional.

		Prahlad Singh Patel	Minister of Panchayat and Rural Development	Is irrigation/ water everything for agriculture? Overuse is wastage. Dispute the conventional ideas of check dams, etc. Apart from technical solution, go for traditional ideas. Pushkar Bhanwar Abhiyaan more than 25000 structures. Irrigation systems. More than 5,000 ponds made. Dry handpumps were used as recharge pumps. Use of gravity for spreading water sources.	Focus on tradition, not on tech.
41	Madhya Pradesh	John Kingsly	Secretary Department of Water Resources	Doubling irrigated area with same amount of water- 170 pressurized piped irrigation. CCA 46.6 lakh ha. 85% water for agriculture use. canal system require permanent land acquisition. Remote sensing and monitoring. The use of at present this remote sensing Technology is used for theoretical Calculation of Actual Vapor Transpiration And the SCADA system is used in all pressurize pipe irrigation network. Requirement of the particular crop and Particular Soil. WEATHER Soil Type Crop and Planted Area Can Decide what type through our irrigation network what type of irrigation schedule has to be done, guide the farmers to use of the advance crops, later linked to the market. Large Scale ET Estimation Basically Sentinel to satellite is being used for Provides high resolution 10 to 20 meters, surface energy balance model so it use solar energy Transpiration and Energy Reflected Back From Back to the Atmosphere and Also Air temperature change to calculate what is the temperature control and also what type and How the Agriculture That We Use Water for It Will Help in Utilizing The Scarce Resource of Water for Other Purposes	NA
		P Narahari	Principal Secretary, Public Health Engineering Dept	Total number of households to be covered- 1,11,88,511 Total covered= 75,25,838 Multiple single and multi village schemes. Tech through OM-Gatishakti portal. MPJN mapped assets on Jal Rekha. Anushravan Module- RFI and daily inspection, Dhara Module- monitoring volumetric data and DWSR, Panchayat Darpan Portal for bill generation. GIS based tubewell management system. Inventory Management System. Numerous digital monitoring initiatives. Disinfection tech needed.	NA
75	Maharashtra	Sanjay Belsare	Secretary Department of Water Resources	5.7 million Hector irrigation potential developed, almost 25 lakh hectare under Microirrigation under various schemes in the Agriculture. irrigation Performance and Service. separate Organization calls Chief Auditor a Headed by Chief Engineer It Independent Organisation under the government of maharashtra. GIS remote sensing, pipe distance Network where there is advantage in Improvement of maharashtra. GIS remote sensing, pipe distance Network where there is advantage in Improvement of the service delivery saving of water. Tembu Iif irrigation. A Lifeline for the Drought Prone Districts of Sangli, Satara and Solapur water is lifted in five stages From a barrage on the Krishna river near Tembu Village in Satara District a total of 22 TMC water is lifted to create irrigation potential for The total project cost is Rs 856 hectares 488 Cr by December 2024 Over R 3867 crores had been invested completing Headworks and Canal System. A key innovation of this project is the Closed pipe distribution system Cropping Patterns of the Tembu Project Includes 20% grapes and pomegranates 15% of Vegetables 20% Pulses with The Remaining 45% allocated to ground nuts and other crops. decentralized system Allow farmers to store and use water Efficiently. 50 to 100 hectare blocks. The Annual Agricultural Produce Before irrigation was ₹ 16.50 crore which has now increased to ₹ 2100 crore per year with an irrigation Efficiency of 70 to 75 per it serves as a Models for Future Projects Across Maharashtra. Rewarded with notable awards. Ultrasonic Sensors. Paani Foundation. NGOs, canal cleaning. Private Sector in Capacity Building. 155 Project to improve the canal discharge level to the design discharge and capacity building.	NA
	(Navi Mumbai)	Kailash Shinde	Municipal Commissioner	1970-CIDCO 29 Village to directly to The Municipal Corporation. Population of 11.2 lakh in 2011 and today it stands 18.5 Lakh. Water Supply and Sanitation System Morbe dam city water source. WTP Bhokarwada. SCADA. southern side of city 450 MLD capacity 25 Landscape Garden. Minimum human intervention. Reduce the Water Concern by almost 20 to 25% by this year. ERP base and e-governance basis. Tertiary Treated water supply now 45 MLD Water is tested. 80% to agriculture. Future growth 4TTP. next 5 years replace fresh water with treated waste water. Circular water economy. Flood mitigation system.	NA

₹ %	ΑN	ΝΑ	
The government focuses on the rejuvenation and conservation of the Nambul River in Imphal, which has been a lifeline for Manipur. Over time, pollution turned it into one of the most polluted rivers in the state, threatening Loktak Lake, a significant Ramsar site. In 2018, the Central Pollution Control Board (CPCB) identified Nambul as one of the nine most polluted rivers in Manipur, classifying a critical 26.4 km stretch under Priority II in the National River Polluted Stretches report. The river originates from the Kangchup Hills and flows 5,537 km before merging into Loktak Lake. It passes through three key zones: 28.98 km in the upper catchment, 9.14 km urbon stretch, which had severe pollution, with biochemical oxygen demand (BOD) levels ranging from 4 mg/L to 52 mg/L, far beyond safe limits. Efforts were focused on 14 municipal wards in Imphal, marking the start of a structured approach to restoration. Under the National River Conservation Plan, a major initiative was launched. Chief Minister N. Biren Single led clean-up efforts. In 2019, the Ministry of Jal Shakti sanctioned 6797.2 crore for national river conservation. Multiple departments collaborated, focusing on wastewater treatment. A 14.5 km pipeline was laid to intercept waste from 72 outlets along the river. Collected wastewater treatment. A 14.5 km pipeline was laid to intercept waste from 72 outlets along the river. Collected wastewater treatment. A 14.5 km pipeline was lead to intercept waste modernised, and 20 community toilet complexes were built. By 2021, the CPCB reported significant improvement, moving Nambul from Priority II to Priority IV. The river's revival reflects strong community community	Meghalaya's water conservation efforts emphasize glaciers, ice caps, and soil as crucial water sources. Springs are primary water sources, but climate change, deforestation, unsustainable agriculture, mining, and rapid urbanization are causing water shortages. Only 24% of Meghalaya's forests are classified as "Very Dense," highlighting the need for conservation. Jhum (slash-and-burn) cultivation is expanding, worsening deforestation and soil degradation. The government has mapped 559 springs, with 747 water sources showing declining discharge rates. The Meghalaya State Water Policy (2019) was the first of its kind in India. Under the Jal Jeevan Mission, 6,457 villages are targeted for functional household tap connections, with 2,699 villages recognized as "Har Ghar Jal" and 81.76% of households covered as of February 2025. Community-based water management involves Village Water & Sanitation Committees (VWSCs) and Water User Associations. Land ownership challenges and high implementation costs affect water supply projects, but efforts continue to integrate conservation with infrastructure development for long-tern sustainability.	Meghalaya's primary water sources are springs, which are crucial for sustaining rivers and serve as key indicators of climate change. Over 80% of the population depends on springs, but a 2016 study found that 50% of them had dried up. Within just three years, 84,000 sq km of forest was lost, worsening the water crisis. Meghalaya, a Sixth Schedule Area, relies heavily on community-led conservation efforts. The state's two major river basins are impacted by population growth, as most people live on ridgelines, directly affecting water sources. A micro-watershed approach is being used for water conservation, with 2,076 watersheds identified, 83 of which are prioritized. The Shillong water supply dam, Umiam Lake, nearly dried up last year, threatening the state's 100% hydroelectricity generation and forcing consideration of importing drinking water. Land degradation due to jhum (slash-and-burn) cultivation remains a major issue despite modernization. Under the lal Jeevan Mission (JM), progress has been made, but many water sources have dried up, making source sustainability a key concern. The Climate Change Adaptive Project, supported by ADB, involves constructing 532 water havesting structures to store 9.08 million cubic meters of water. Another initiative, the Payment for Ecological Services program (744 crores), incentivizes communities to conserve forests. The externally aided MEGA-RISE project focuses on conserving Greater Shillong's watershed areas. The Spring Shed Management program is integrated into watershed development projects, rejuvenating 5,000+ springs and treating 70,000+ hectares of land. The Critical Source Sustainability Project supports both rural and urban water schemes, covering 67 critical sources and constructing 356 water harvesting structures. Climate Adaptive Community-Based Water Harvesting, supported by ADB, includes 532 structures covering 12,000+ hectares of catchment area. Meghalaya emphasizes community-driven conservation efforts and considers springs as sacred, advocating their pro	
	Minister Soil and Water Conservation	Commissioner Soil and Water Conservation	
PPT	Marcuise N Marak		
Manipur		Meghalya	
16		17	

is 8th im per iment is ind	rvoir only NA inization.	of instream on of more sts 5 years- fmoney in The tribal deity is indicative of the am, Deo ation of mitras, no urd-reform	709- Toll free able. High NA et clean S.S.	pply al areas in han 10 colum water EC and embers, evolution t issues.
In Odisha the occurance of floods and cyclones is very common. Area of 1.55 lakh sq., km which is 8th largest by area and 11 th in population. 50% of population relies on agriculture. Rainfall is 1500 mm per year. Distribution is uneven. Aim to become water secure state by 2036. To ensure this, the government is working on projects on water conservation and water governance with new digital management and monitoring. 18 billion cubic mstorage capacity has been developed. Groundwater capacity has also been developed but this is not enough for the demand. Govt is making new structure by increasing capacity, building dams, rainwater harvesting structures, reservoirs, etc. Pain Panchayat, participitatory irrigation management schemes have been made to develop climate resilience but still it is a serious challenge. Integration of waters had management, soil coservation, aforestion to increase ground water level. Women self help groups are playing a major role in promotion of water conservation practices. More than 40,000 pani panchayats are active in area 24.57.1akh hectare area and 24,500 communities participate. In 2019, only 3.5% rural households had tap water connection while now 76.4% have that connection. The target is to acheive 100% coverage by March 2027. Last mile coverage is being prioritized. 77 fully functional water testing aboratories have been sexbalished. 94000 self help groups are also involved in this testing. Technical interventions like desalination, waste water recycle and smart irrigation. National Water Innovation hub has been proposed and startups for the same purpose have been proposed.	16% population 2.5% land and 4% water 4000 BCM water in India. Out of 1,869 BCM water reservoir only 1,122 BCM can be expected due to topographical factors. Sediment management for reservoir optimization. Numerous sediment removal techniques were discussed. Khushi Sinchai yojana- har khet ko paani. Minimize water wastage in irrigation. UGPL distribution system	Average annual rainfall- 1452 mm. Spatial distribution is intense and rainfall is skewed, water storage- 210 large dams, 89058 public waterbodies. Initiatives- Expedition of ongoing large dams, completion of instream storage structure across areas. Gating 50 ungated reservoirs, intensifying catch the rain, construction of more check dams, renovating water bodies, intrastate river linking. Great progress in MMI projects in last 5 years-involve district collectors from beginning. Piped canals in place of open canals, pumped in a lot of money in these projects. Tender committees, eg. Indravati Lift Canal, Gangadhar Meher LIP, Lower Indra dam, Deo dam, etc 8 projects taken up for irrigating 0.93 lath ha. Check dams- 16664- all geotaged. Renovation of MIPs, 48% ground water use. 10000 tanks for recharging ground water- Rainwater harvesting, Jal mitras, no critical blocks, many jal panchayats, using undergroung pipelines, rotational irrigation. Way forward- reform measures, adding technology.	2019-50% household had tap facility in 2019 and had achieved har ghar jal well before target. 2009-grievance redressal system for water related issues was present. 99.70% complaint resolution rate. Toll free number for complaints awailable. Digital tracking also available. IOT and SCADA facilities available. High women participation. Atleast 50% women participation ensures. Groundwater has high Sodium Hypochlorite concentration. 15 Quality Assurance scheme are ongoing. 25 lakh households will get clean and safe drinking water. Require funding for success and smooth implementation of the 15 projects.	50,362 sq. km land, mostly fertile, 3.42 million rural householdshave FHTC. 8,532 rural water supply schemes. 55% schemes are handed over to the panchayat. Commitment for 70 IPCD supply in rural areas in 2014. 382 habitations have 24X7 water supply while 4881 habitations get water supply for more than 10 hours. It helps in careful use of water. Equitable and fair distribution. Supply chain network for Sodium Hypochlorite for disinfection. 59650 women trained to use visla and kits. 31 labs across state and water quality montoring through 3-ter infrastructure. Model bye laws of 2015. GPWSC- 50% women. IEC and capacity building, participation, flexibility, local administration, active and competent GPWSC members, handholding. Case studies of villages. Challenges-difficulty in handing schemes to panchayats, devolution vs privatization. Low cost recovery, perception of difficulty of management schemes, enforcement issues. SNK system for previous entry programment schemes, enforcement issues.
Chief Minister	Chief Minister	Additional Chief Secretary of the Departments of Water Resources	Minister for Revenue, Rehabilitation and Disaster Management of Punjab	Principal Secretray Water Supply and Sanitation
Mohan Charan Majhi	Mohan Charan Majhi (2nd address)	Anu Garg	Hardeep Singh Mundian	Nilkanth S. Avhad
Odisha	NOT STATE SPECIFIC. Speech as the chair.			Punjab
18				19

₹Z	NA	NA
Culf of Mannar Conservation (Tamil Nadu) Tamil Nadu's southeastern coast has the Culf of Mannar, a shallow bay with 21 uninhabited islands, extending from Rameswaram to Kanyakumari. It has rich biodiversity, including coral reefs, seagrass beds, and man manual manual properties and manual properties and engangeries. It has rich biodiversity, including coral reefs, seagrass beds, supporting tourism and livelihoods. Climate change, rising temperatures, and human activities like overharvesting, industrial waste, and destructive fishing have severely affected the ecosystem, leading to coral bleaching. To protect it, the Tamil Nadu government has undertaken conservation measures with expert refer researchers. Corar leabilitation is done using fragment transplantation and artificial substrates. Multi-purpose artificial modules were installed around sinking islands to prevent submergence. Seagrass and mangrove plantations have shown positive results. Alternate livelihood programs support fishermen shifting away from unsustainable fishing. A unique initiative, plastic check posts, prevents plastic entry into the Gulf of Mannar, promoting eco-friendly alternatives. Tapi River Rejuvenation (Gujarat) The Tapi River Rejuvenation (Gujarat) The Tapi River purification project to control pollution and restore the river. The project covers and 85 km stretch from Kakrapar Barrage to ONGC Bridge in Surar. Objectives include preventing further damage, improving water quality, and implementing long-term wastewater management for villages and towns along the river. The plan ensures reared wastewater is reused for irrigation and horiculture. Measures include preventing fruther damage, improving SWIDA) expanded sewer systems in surrounding towns and villages. The project, costing ₹972 rerore, is a collaboration between the central and Gujarat governments, SUDA, and SMC. Future plans include supplying treated wastewater into the river. The Sura Municipal Corporation (SMC) intercepted this and ungeraded existing sewage treatment	312 per sq. km population density. 276.94 lakh acres 166.98 lakh acres. Irrigation potential 73.57 lakh acres. 906.3mm rainfall. 54 lakh acre balance IP to be created. 34 major and 39 medium projects taken till date. 42 completed 31 ongoing. 2.98 lakh crores expenditure incurred. balance 90,100 crore. capacity of IP 904 TMC. AMRSLBC 13.6 TMC capacity. Dindi LIS 25.64 TMC capacity. Palamuru Ranga Reddy LIS approx 68 TMC. modernizing canal networks. mior irrigation works. 5,300 crores. desilting, check dams, off takes, micro-irrigation. Vanmahostavam cover from 224, 633%. 3.29 m rise in ground water from 2014-15 to 23-24. Requests- KWDT 2 intervention for rigisule settlement, water allocation for projects like sectaram sagar etc. funding request in place of high interest short term loans. Cleaning Musi river, interventions in NDSA approval. Resolution between Telangana and Andhra for solving issues.	100 I per capita per day. Floods and droughts- both abundance and scarcity. Mission maryada. Borewells, handpumos, peipelines, etc. 149 multi village scheme. Stabilize water supply. Identifying and utilizing local water sources. 4 lakh houses not covered in mission maryada- govt has brought that also under the scheme. Flood management. Toll free number. Funding for the missions. 5000 cr annually on water. Did not get money from center. Want 16000 cr atleast from govt.
	Minister for Irrigation, Food & Civil Supplies	Minister of Rural Water Supply
PPT	Nalamada Uttam Kumar Reddy	Dansari anasuya
Tamil Nadu	Telangana	
22	23	

V Z	NA	NA	NA
Rajasthan Ram Jal Setu Link Yojana was inaugrated for irrigation in 4 lakh hectare of land. Joining of rivers and tributaries as method for sustainable water management. Rajasthan has water scarcity but in Karmbhoomi se matrabhoomi plan, 1,60,000 tubewell in 45000 villages installment plan has been established. Thanked Madhya Pradesh and Haryana for their cooperation wrt their rivers with Rajathan. Rajasthan is skilled in water management at national level. Long term policies are the requirement of the hour. Sprinkler and other micro irrigation system has been lighly effective in Rajasthan. About 50% water can be saved by these techniques. Villages should be educated about the same to promote agricultural output as well. Crops that require lesser water should also be promoted like Bajra, dal, etc. This will also increase the earnings of the farmers. Urban water planning is another aspect where due to over population density where water demand increases needs to be accepted and adapted to accordingly. Futuristic planning needs to be done when laying down pipelines, etc. Water recycling and quality improvement should also be promoted. Mixing of traditional ways with modern technology. Rajasthan govt is also following the same for Rainwater harvesting by incorporation traditional techniques like khadil, taka, nadi, etc. are being used.	Hilly area. 2023 cloud burst. Help for the water resource restoration from that. 6 months frozen ice. 6 months landslide etc. Bijli Paani, sadak. Organic water. Water donation.	7096 sq km. 227 high altitude lakes, more than 100 rivers and streams. 2 major rivers- Teesta and Rangit. High to very high rainfall. Dhara Vikas mission- 100 pits per hectare. More than 80% householdss depend on springs for water. Gravity flow supply systems. Isolated mid hills- sensitivity needs to be considered. 2008 onwards- recharge of spring water initatives have been taken. Local capacity building- Para hydrogeologists. People are trained for water testing. 8 steps methodology from resource mapping to monitoring and evaluation. Collection of baseline information manually. Multiple hands-on field experiences required. Aquifer focus after 2011. Isotope studies for recharge area. Critical springs hydrograph. Concretization of Tamley Pokari. Revival of Suke Phokari. Recharge structures under MGNREGA. Village water security plan carried out. RS & GIP planning. Android application for mapping. Handbooks provided. Places where implementations were not possible.	649 Urban Local bodies. water requirement Greater than 70 lpcd for regular needs.water demand is higher than potential. The Famil Nadu government is focusing on restoring water balance as 73% of the state is hard rock terrain, with 47% of its water sources categorized as over-exploited or critical. The hydrological stress is being addressed by promoting wastewater reuse and a circular water economy. A wastewater reuse policy launched in 2019 aims to reduce reliance on freshwater, with urban sewerage schemes, STPs, and greywater usage being expanded under various government initiatives. Chemai was the first city in India to supply secondary treated water to industries in 1991, and since 2019, wastewater supply to industries has significantly increased. The state plans to set up 14 TTRO plants with a 1002 MLD capacity, along with a 10 MLD ultrafiltration plant for lake recharge. Jal Jeevan Mission initiatives include centralized smart metering systems to improve water management and revenue collection. Tamil Nadu has been a pioneer in rainwater harvesting since 2002 and is now strengthening efforts with technical solutions, making rainwater structures mandatory in building regulations. Hydrogeological management maps have been created for groundwater conservation and handed over to relevant departments. Policies focus on reducing leakages, improving efficiency, and conducting energy audits for high-power pumps, revealing potential savings with energy-efficient replacements. Comprehensive planning integrates rural and industrial water supply to optimize costs and sustainability. The state received the First Prize in Functional Assessment 2022 from the President of India. Future plans include small desalination plants to ensure water security, with Chemai expanding its desalination capacity. The Tamil Nadu Water Supply Board maintains 1,286 borewells for groundwater assessment to aid sustainable water resource management.
CM	Minister of water resources and public health engineering	Secretary Department of Water Resources	Mt dm
Bhajan Lal Sharma	Ven. Sonam Lama	Lhendup D. Lamtha	Kiran Gurrala
Rajasthan		Sikkim	
20		21	

₹Z	ΝΑ	NA
Tripura 3rd smallest state. 10,491 sq km area. more than 70% forest covered. Primary occupationagriculture. State is giving priority to more irrgiation projects to boost agriculture and help farmers double their income. Total cultivable land is only 25%. Irrogation cover is only in 47% of cultivable land. Target is to achieve 80% irrigation cover. Due to first flowing rivers and limited water storage capability, there is little scope for surface water based irrigation projects. Therefore, there are structures for minor dams, and rainwater harvesting systems. There are 98 identified sites for minor project across 30000 hectare and 14 initiated projects. Tripura is blessed with abundant ground water due to long rainfall periods and high forest cover. Rate of extraction is also 9.48% as compared to 60.50% national average. Deep and small tubels have been used for irrigation as well as drinking purposes. Since the launch of Jal Shakti mission, the state groundwater has increased from 1.063 billion cubic m in 2023 to 1.18 billion cubic m. More than 45000 water structures have been developed under tha jal shakti mission. 975 annit sarovars have been developed in the 8 districts of the state. Several 14th century heritage structures have been restored making them place of leisure and tourist attraction. In 2019, only 24000 i.e. 3.26% households had tap water connection. In 2025 6.38 lakh i.e. around 84.85% households had tap water connection which is greater than the national average of 79.76%. It has enhanced the ease of living in rural areas. Innovative water supply ideas based on commissioned and 251 are in progress. Most of ground water is high in Iron concentration. The acceptable limit is 0.3 mg/l. As a result Iron removal plant is being installed. Due to this financial burden on the state has increased. To bridge the gap, 126.2 jan intrians have been trained. 4347 schools- 96.34% and 8435 - 96.10% anganwadi centers have freshwater availability and the target is to achieve 100% coverage by Sept 2025. Assistance	remote Sensing Based Irrigation Collaboration with Government ISRO, NRC Sharda Saryu and Ganga Canal in the state Drone mapping and satellite in the system Monitoring irrigation. Distribution was improved to save water and water is made available to farmers on time. Mata dam situated on Berwa river in Hua state in the system on Tala Dam and Sar Canal Automatic gate control system has been installed. The flow is controlled in real time This brings transparency in water distribution. Smart Drip and Sprinkler systems are promoted which consumes water has decreased by 30 to 40 per cent and the crop Production has increased. There are more than 1400 water consumers, water Consumer committees have been formed in The committees decided which villages When and how much water should be supplied to the ensuring the availability of water and Disputes have reduced. There are several major canal systems in the state Such as Ganga Canal, Sharda Eastern Yamuna Canal. Digital flow meters have been installed. Combined various govt. policies. More than 500 Ponds have been reconstructed. The water level has risen by 10 feet. Development of Bandhav Jala as a sustainable tourism spot. The State Government has started a programme encouraged to help the local people. Employment was also found, socio-economic development and water-based Ajeev's vote bank was transferred to Uttar Pradesh government. Similarly 1500 people are staying at the banks of Navavi Ganga Mission. Developed more than 50 organic farming villages	identified floodplain zones for major rivers to control encroachment and pollution. The National Green Tribunal's directives have led to scientific determination of flood zones for rivers like Ganga, Yamuna, Gomti, Ramganga, Betwa, Ghagra, and others, using high-resolution remote sensing and hydrological data. The government is working towards economic and social development through water security, promoting rainwater harvesting, and strengthening community-based water management. Under Water Vision 2047, India aims to set a global benchmark in water conservation. The National Mission for Clean Ganga (NMCG) and the National Institute of Urban Affairs (NIUA) launched the Urban River Management Plan (URMP) in 2020, focusing on sustainable river-sensitive urban development. Five Indian cities have developed URMPs, with Chhatrapati Sambhaji Nagar's Kham River Restoration Initiative receiving global recognition. The River Cities Alliance (RCA), launched in 2021, provides a platform for Indian cities to collaborate on sustainable river management. Starting with 30 cities, RCA has grown to over 145 river cities, developing knowledge resources and capacity-building initiatives. Supported by the World Bank, RCA aims to implement 60 new URMPs, advancing urban river rejuvenation and fostering sustainable urban
Chief Minister	Jal Shakti Minister	Jal Shakti Minister
Manik Saha	Swatantra Dev Singh	Swatantra Dev Singh
Tripura		Uttar Pradesh
24		25

	PPT		Flood plain zoning in Uttar Pradesh divides its rivers into eight basins for management, with 38 rivers flowing through the state. The process involves satellite maps and hydrological data from the Uttar Pradesh Remote Sensing Application Centre, Lucknow. Surveys analyze flood levels over five, 25, and 100 years using mathematical models and hydraulic studies. Floodplain areas are determined by superimposing satellite and hydrological data. So far, zoning has been implemented for 22 rivers, including the Ganga, Yamuna, and Solani, with 15 more in progress and four yet to start. Zoning classifications include the Private Zone (no permanent activities, only temporary ones like parks), the Regulatory Zone (permanent structures allowed for public institutions), and the Warning Zone (flood-prone areas for 25 to 100-year floods).	Flood Plain Zoning
	PPT		Uttarakhand, a hill state, is the origin of major rivers like the Ganga and Yannuna, which sustain North India by providing drinking water and supporting agriculture. However, climate change, erratic weather patterns, and natural disasters have led to the depletion of water sources, creating challenges for people in mountainous regions. To address this, the Uttarakhand Government established the Spring and River Rejuvenation Authority (SARA) to protect and revive various water bodies, including small and large rivers, reservoirs, and rain-fed streams. SARA focuses on scientific identification of rainwater storage, sustainable management of water sources, and local community participation for conservation. The initiative employs modern GIS technology, GPS, and drones for terrestrial assessment, monitoring flow rates, and water quality. Geo-hydrological studies and mapping help identify recharge areas, forming the basis for long-term conservation plans. To ensure effective implementation at the grassroots level, Stream Naula Conservation community involvement. Water being essential for human life, the Uttarakhand government's efforts in natural resource conservation through SARA will play a crucial role in addressing water scarcity, ensuring sustainable irrigation, and securing the future of both drinking water and agricultural needs in the state.	
H	Manas Ranjan Bhunia	Manas Ranjan Bhunia and Waterways	Three Major Basin Areas on the North Side Brahmaputra the major part is Ganga and South West Side is swarnarekha. Major Flowing from north to south if you look into the Agro Climatic Zones The State Can Be Divided into six zones starting from north hill zones than terai Teesta Elwill Zone. Old Elvil Zone, Gazette, Laterie zone, coastal saline zone agroclimatic conditions help in planning of all the major and minor laterite zone, coastal saline zone agroclimatic conditions help in planning of all the major and minor system in the state is divided into major and minor is looked after by the Irrigation Water Ways Department and the the minor is looked after by water Resources Investigation Development Department. Use of Remote Sensing Data. 77% cultivable by irrigation 60% surface water, difficulties is the lack of Maintenance Lack of Accountability Performance Monitoring Absence of Stakeholders Participation. Registered under the Society Act 8000 schemes have been Implemented through the Water Use Association. 3500 WUAs. 1.5 Lakh farmers participation. Women participation. support services, eduction in Single Crop area increased in double crop area and increase in triple crop area the Cropping intensity has gone up from 190 to 2049. on pilot bais- private participation in Damodar Valley Corporation. divided into 11 components All components have been given to the irrigation Service providers. KPl And KMI Have Been Very Clearly Identifical. Kharif increase from 1.78 lakh to 3.52 hectare in case of Ravi the increase is 57 per in case of burrow it is Around 32%. knowledge gap. Digital Dashboard. Remote sensing	Discussed significantly on WUA
	Pulak Roy	Minister of Public Health Engineering	Jal Dharo Jal Bharo, matir srishti project to make unused land fertile. Problems- recycling of water lost in distribution, grey water management. Legislation on different water governance, enforcement and implementations. Recovery of natural and traditional bodies for water storage.	Streamlining water-related legislation.